



APPLICATION ACCEPTED: September 13, 2011
PLANNING COMMISSION: February 23, 2012
PLANNING COMMISSION DECISION: June 14, 2012
BOARD OF SUPERVISORS: not scheduled

County of Fairfax, Virginia

May 31, 2012

STAFF REPORT ADDENDUM

APPLICATION RZ/FDP 2011-MA-029

MASON DISTRICT

APPLICANT: Neighborhoods VI, LLC

PRESENT ZONING: R-2, HC

REQUESTED ZONING: PDH-4, HC

PARCEL(S): 71-2 ((1)) 36, 71-2 ((13)) 1, and 71-2 ((10)) 17A

ACREAGE: 8.79 acres

OPEN SPACE: 40.1%

PLAN RECOMMENDATION: Residential at 3 to 4 dwelling units per acre (du/ac)

PROPOSAL: The applicant seeks to rezone 8.79 acres from R-2 and HC (Highway Corridor Overlay) to PDH-4 (Planned Development at 4 du/ac) and HC to permit the development of 29 single family detached dwelling units at an overall density of 3.30 du/ac.

STAFF RECOMMENDATIONS:

Staff recommends approval of RZ 2011-MA-029, subject to the execution of proffers consistent with those found in Attachment 1 of this report.

Staff recommends approval of FDP 2011-MA-029, subject to the development conditions in Attachment 2 of this report.

William O'Donnell

Staff recommends approval of a waiver of the 600 foot maximum length for a private street.

It should be noted that it is not the intent of staff to recommend that the Board, in adopting any conditions proffered by the owner, relieve the applicant/owner from compliance with the provisions of any applicable ordinances, regulations, or adopted standards

It should be further noted that the content of this report reflects the analysis and recommendation of staff; it does not reflect the position of the Board of Supervisors.

The approval of this rezoning does not interfere with, abrogate or annul any easement, covenants, or other agreements between parties, as they may apply to the property subject to this application. For information, contact the Zoning Evaluation Division, Department of Planning and Zoning, 12055 Government Center Parkway, Suite 801, Fairfax, Virginia 22035-5505, (703) 324-1290.

N:\ZED\Rezoning\RZ 2011-MA-029 Callaway Residential\Report\RZ 2011-MA-029 - Callaway - Staff Report Addendum Cover.doc



Americans with Disabilities Act (ADA): Reasonable accommodation is available upon 48 hours advance notice. For additional information on ADA call (703) 324-1334 or TTY 711 (Virginia Relay Center).

Rezoning Application


RZ 2011-MA-029

Applicant: NEIGHBORHOODS VI, LLC
Accepted: 09/13/2011
Proposed: RESIDENTIAL
Area: 8.79 AC OF LAND; DISTRICT - MASON
Located: NORTHWEST QUADRANT OF THE
INTERSECTION OF WILLOW RUN DRIVE
AND LITTLE RIVER TURNPIKE
Zoning: FROM R- 2 TO PDH- 4
Overlay Dist: HC
Map Ref Num: 071-2- /01/ /0036 /10/ /0017A
/13/ /0001

Final Development Plan

FDP 2011-MA-029

Applicant: NEIGHBORHOODS VI, LLC
Accepted: 09/13/2011
Proposed: RESIDENTIAL
Area: 8.79 AC OF LAND; DISTRICT - MASON
Located: NORTHWEST QUADRANT OF THE
INTERSECTION OF WILLOW RUN DRIVE
AND LITTLE RIVER TURNPIKE
Zoning: PDH- 4
Overlay Dist: HC
Map Ref Num: 071-2- /01/ /0036 /10/ /0017A
/13/ /0001



SUMMARY OF APPLICATION

The applicant, Neighborhoods VI, LLC, filed a rezoning application (RZ/FDP 2011-MA-029) on Tax Map Parcels 71-2 ((1)) 36, 71-2 ((13)) 1, and 71-2 ((10)) 17A, from R-2 and HC (Highway Corridor Overlay) Districts to PDH-4 (Planned Development at 4 dwelling units per acre (du/ac) and HC Districts to permit residential development with single family detached dwelling units. A map of these tax map parcels is located in the front of this Staff Report Addendum.

The Staff Report, recommending approval of the application, was published on February 8, 2012, and concluded that the proposed residential development with 35 single family detached dwelling units at an overall density of 3.98 du/ac was in conformance with the Residential Development Criteria of the Comprehensive Plan and met the requirements of the Zoning Ordinance. The application included restoration and preservation of a headwaters area on the southern portion of the site (which is a Resource Protection Area (RPA)), 25 foot minimum wide buffers along the periphery of the site with additional buffering to the northwest, southeast and east boundaries, 30.2% open space, two pedestrian amenity areas, significant tree preservation with tree transplanting, right of way dedication for the future expansion of Little River Turnpike and an underground stormwater facility with BMP facilities which met the Public Facility Manual requirements for detention and stormwater quality. Graphic 1 below shows an illustration of the Conceptual Development Plan/Final Development Plan (CDP/FDP) with 35 single family detached dwelling units.

Graphic 1 – Original Proposal - 35 single family detached dwelling units



On February 23, 2012, the Planning Commission held a public hearing for the subject application and deferred their decision to June 14, 2012, to allow time for the applicant to revise their submissions to address concerns about the proposed density that were identified at the hearing. Since the public hearing, the applicant has worked with staff to modify their application and has proposed several proffer changes, which are included in Attachment 1 (with changes black-lined from proffers included in the original Staff Report.) The applicant also revised the CDP/FDP, which is contained in Attachment 3 and now dated July 2011 and revised through May 16, 2012. Proposed development conditions are included in Attachment 2. A more detailed analysis of the proposed changes follows.

ANALYSIS

The applicant revised their proposed CDP/FDP with the following generalized changes, which are listed below and highlighted in Graphic 2.

- Reduced the total number of single family detached dwelling units from 35 (3.98 du/ac) to 29 (3.30 du/ac). This reduction resulted in the elimination of two single family dwelling units along the western boundary, three dwelling units along the eastern boundary and one dwelling unit from the center of the private loop.
- Modified the general configuration/layout of site from a “b” shaped configuration to more of an “s” shaped configuration. Access to the property continues to be provided from Willow Run Drive. The applicant also continues to propose a private road, which would extend into the site and create a private loop with single family detached dwelling units located on both sides of the road. The loop road is now proposed to handle two-way traffic as opposed to the previously proposed one-way.
- Decreased the number guest parking spaces from 36 guest spaces to 33. However, this decrease equates to an increase in the guest parking space to proposed dwelling unit ratio, which is now proposed to be 1.13 guest spaces per dwelling unit instead of the previously proposed 1.02.
- Increased the landscaping buffer depth along the southeastern property boundary from 25 feet to 30 feet.
- Increased the total open space from 30.2% to 40.1%.
- Relocated the amenity seating area which was located to the north of the proposed stream restoration area on the south side of the property to a more central location on the site.
- Replaced the original proposed underground stormwater detention facility with an extended detention dry pond located to the north of the stream restoration area. Additional amenity features including ornamental landscaping and seating are proposed to the north of the dry pond to help activate the space for passive

recreation. No changes were proposed to the stream restoration plans. The applicant continues to propose restoration and preservation of a headwaters area on the southern portion of the site

Graphic 2 – Revised Proposal - 29 single family detached dwelling units



In addition to the proposed CDP/FDP changes, the applicant refined the proffers which include the following modifications:

- Proffer 1 (Substantial Conformance): Revised to reference the revised plans dated July 2011 revised through May 16, 2012.
- Proffer 3 (Rears of Units 11-13 and 19-24): Renumbered the Units
- New Proffer 4 (Lot 14): Commitments added to provide a hip-style roof as shown on Sheet 17 of the CDP/FDP for Lot 14 and to finish the rear of the unit with materials that match those on the front. In addition, no raised deck or second floor deck will be provided for this unit.
- Revised proffer numbers: The applicant renumbered all proffers after the addition of the new Proffer 4 referenced above.
- Proffer 6 (Lot Yield): Revised to reflect the 29 units now proposed.

- Proffer 12 (Garage Conversion): Clarified to stress that the conversion of garages to living space will be prohibited.
- New Proffer 13 (Parking): Added a proffer to prohibit the parking of boats and/or recreational vehicles within the community.
- Proffer 14 (Lot Typical, Decks and Similar Appurtenances): Revised to clarify that porches (including screened in porches) or sunrooms may be permitted in the rear yard in the area identified as "Deck, Addition or Accessory Feature Area" shown on the lot typical included on Sheet 3 of the CDP/FDP.
- New Proffer 16 (Retaining Walls): Added to specify that retaining walls will be made of stone or brick materials as detailed on Sheet 16 of the CDP/FDP.
- Proffer 22 (Guest Parking Spaces): Clarified to prohibit recreational vehicles, RVs, boats, or trailers in guest parking spaces.
- Proffer 23 (Construction Access and Hours): Reduced the construction hours from the original proposal of:
 - 7:00 am to 9:00 pm Monday through Friday and 8:00 am to 7:30 pm on Saturdays to:
 - 7:00 am to 7:30 pm Monday through Friday and 8:00 am to 7:00 pm on Saturdays.
- Proffer 25 (Stormwater Management Facilities and BMP): Revised to reflect the removal of the underground system in favor of the dry detention pond. In addition, the applicant acknowledged that, if warranted by final engineering, minor modifications to the size, location and configuration of the dry detention pond may be made in connection with subdivision plan approval; provided however, that such changes shall not serve to diminish the effectiveness of any required screening and landscaping. Similarly, the Applicant acknowledges that such minor modifications may result in a loss of density.
- Proffer 26 (Stormwater Management Facilities and BMP Maintenance): The applicant has acknowledged that, should the approved subdivision plan reflect any stormwater facilities not maintained by Fairfax County, an escrow for the HOA will be established to provide for the future maintenance of such improvements, and a contribution will be made to a reserve fund for the future replacement of the underground facility, which will receive annual deposits from the HOA; the amount of the escrow shall be approved by DPWES.
- Proffer 44 (Park Authority Contributions): Revised to reflect the decrease in the number of proposed units.

- Proffer 45 (Parks and Recreation): Expanded the type of recreational amenities features shown on the CDP/FDP to include play areas and gazebos.
- Proffer 47 (School Contributions): Revised to reflect the decrease in the number of proposed units.

Please see Attachment 1 for a copy of the revised proffers, which shows all changes black-lined from proffers included in the original Staff Report.

Transportation (Attachment 4)

During the public hearing, the Planning Commission requested written documentation from Fairfax County Department of Transportation explaining why the proposed access from Willow Run Drive is the preferred alternative for access to the site. Attachment 4 includes a memo from FCDOT. Four access alternatives were identified and included:

- 1) Access to existing service road,
- 2) Access to the existing service road and extension of the service drive to Willow Run Drive,
- 3) Access to Randolph Dr. at the southern portion of the site, and
- 4) Shared access with the commercial property to the west

All four of these alternatives had significant issues. The main issues with Alternatives 1 and 2 were that when Little River Turnpike is widened to six lanes, the existing service road would be eliminated and access would be provided directly to Little River Turnpike. Neither FCDOT or Virginia Department of Transportation (VDOT) could support this situation because the access would not meet VDOT's access management standards and would not give the site access to a traffic signal. In addition, if the existing service road was extended to Willow Run Drive, it would be too close to the traffic signal soon to be located at the intersection of Little River Turnpike and Willow Run Drive, which would create significant conflicts with traffic patterns. Alternative 3 would be supported by VDOT, but not Fairfax County, since the access would go through the Resource Protection Area (RPA). According to the Chesapeake Bay Preservation Ordinance, roads may be exempt from RPA if an RPA encroachment exception shows that there is no other viable alternative. However, there is a viable access alternative from Willow Run Drive as shown on the CDP/FDP. Alternative 4 is also supported by VDOT, but only if access is also provided to the traffic signal (soon to be located at intersection of Little River Turnpike and Willow Run Drive) as currently shown on the CDP/FDP.

Therefore, after due consideration, staff determined that the proposed access from Willow Run Drive as shown on the CDP/FDP is the preferred alternative because it is not temporary, it would not traverse an RPA and it would give the community access to a traffic signal.

Stormwater Management (Attachment 5)

The applicant proposes to replace the original underground stormwater detention facility with a dry detention pond. Staff from the Department of Public Works and Environmental Services reviewed the revised plans. A copy of their memo is provided in Attachment 5. Several of the comments listed in memo would be addressed during subdivision review. Five comments required additional revisions, which include the following:

- 1) The CDP/FDP shows two alternatives for stormwater detention; an underground system and a dry pond,
- 2) Storm drains discharging to the dry pond with pipes constructed underneath a retaining wall are not approvable,
- 3) Trees will not be allowed to be planted within 5 feet of a storm drainage easement,
- 4) Proffer 41 should be an Invasive Plant Species Management Plan only, and
- 5) A proffer should be provided to address the dry pond's proximity to the RPA. If during final engineering, the extent of the pond needs to be expanded, it cannot be expanded into the RPA, and may only be expanded to the north by potentially eliminating Lot 19.

The applicant revised their proposal to address these comments.

CONCLUSIONS AND RECOMMENDATION**Staff Conclusions**

Staff concludes that the subject application continues to be in conformance with the Residential Development Criteria of the Comprehensive Plan and continues to meet the requirements of the Zoning Ordinance. Staff feels that the proposed revisions listed in this report significantly improved the overall layout of the site from that which was originally proposed.

Recommendations

Staff recommends approval of RZ 2011-MA-029, subject to the execution of proffers consistent with those in Attachment 1.

Staff recommends approval of FDP 2011-MA-029, subject to the development conditions in Attachment 2.

Staff recommends approval of a waiver of the 600 foot maximum length for a private street.

It should be noted that it is not the intent of staff to recommend that the Board, in adopting any conditions proffered by the owner, relieve the applicant/owner from compliance with the provisions of any applicable ordinances, regulations, or adopted standards.

It should be further noted that the content of this report reflects the analysis and recommendations of staff; it does not reflect the position of the Board of Supervisors.

ATTACHMENTS

1. Proposed Proffers
2. Proposed Development Conditions
3. Revised CDP/ FDP
4. FCDOT Analysis Addendum
5. Stormwater Management Analysis Addendum

**NEIGHBORHOODS VI, LLC
CALLAWAY**

**RZ 2011-MA-029
PROFFERS**

~~January 29,~~May 14, 2012

Pursuant to Section 15.2-2303(a) of the Code of Virginia, 1950, as amended, the property owner who is the Applicant in this rezoning proffer that the development of the parcels under consideration and shown on the Fairfax County Tax Maps as Tax Map Reference – 71-2-((1))-36 and 71-2-((10))-17A and 71-2-((13))-1 (hereinafter referred to as the "Property") shall be in accordance with the following conditions if, and only if, said rezoning request for the PDH-4 District is granted by the Board of Supervisors of Fairfax County, Virginia (the "Board"). In the event said application request is denied or the Board's approval is overturned by a court of competent jurisdiction, these proffers shall be null and void. The Owners and the Applicant ("Applicant"), for themselves, their successors and assigns, agree that these proffers shall supersede any and all previously approved proffers or Special Exception conditions and shall be binding on the future development of the Property unless modified, waived or rescinded in the future by the Board, in accordance with applicable County and State statutory procedures. The proffered conditions are:

I. GENERAL

1. Substantial Conformance. Subject to the proffers and the provisions of Article 18 of the Zoning Ordinance, under which minor modifications to an approved development plan are permitted, the development shall be in substantial conformance with the Conceptual/Final Plan entitled "Callaway" (CDP/FDP), containing twenty four

(24) sheets prepared by BC Consultants dated July 2011 and revised through ~~January 27,~~May 16, 2012.

2. Architecture. The architectural design of the dwellings shall be in substantial conformance with the bulk, mass and type and quality of materials and elevations shown on sheet 17 of the CDP/FDP. The primary building materials exclusive of trim shall be limited to brick, stone, cementitious siding, shingles or other similar masonry materials. Minor modifications may be made with the final architectural designs provided such modifications are in substantial conformance with the elevations shown on the CDP/FDP.

3. Rears of Units ~~1411-1713~~ and ~~23-3019-24~~. The rear facade and architecture of units ~~1411-1713~~ and ~~2319-3024~~ as shown on the CDP/FDP shall include the following:

- Within units ~~1411-1713~~, a minimum of one unit shall incorporate rear dormers or gables into the roof architecture.
- Within units ~~2319-3024~~, a minimum of three units shall incorporate rear dormers or gables into the roof architecture.
- **Two different roof styles shall be used.**
- There shall be a minimum of two exterior colors used with no two adjacent units having an identical color.
- ~~All paint, siding and other building materials shall be of a flat non-glare finish.~~
- Decorative window treatments will be varied among the units. The treatments may include but are not limited to: trim, shutters and ornamental features.
- All decorative fixtures shall be of a type and style consistent with those used on the front facade.

4. **Lot 14. The roof style on Lot 14 shall be a hip style roof, similar to that shown on Sheet 17 of the CDP/FDP. The south side and rear of the house on Lot #14 shall be finished with materials proportional to and matching those on the front of the unit. There shall be no raised deck or second floor deck on this unit. There shall be no third floor living space permitted on this house.**

5. 4.-Minor Modifications. Minor modifications from what is shown on the CDP/FDP and these Proffers, which may become occasioned as a part of final architectural and engineering design, may be permitted as determined by the Zoning Administrator in accordance with the provisions set forth in Article 16 of the Zoning Ordinance.

6. 5.-Lot Yield and Uses. The development shall consist of a maximum of thirty five (35)~~thirty five~~ **twenty-nine (29)** single-family detached dwelling units.

7. 6.-Establishment of HOA. Prior to record plat approval, the Applicant shall establish a Homeowners Association (HOA) in accordance with Sect. 2-700 of the Zoning Ordinance for the purpose of, among other things, establishing the necessary residential covenants governing the use and operation of common open space, stormwater management facilities and other common facilities of the approved development and to provide a mechanism for ensuring the ability to complete the maintenance obligations and other provisions noted in these proffer conditions.

8. 7.-Dedication to HOA. At the time of record plat recordation, open space, common areas, private roadways, and amenities not otherwise conveyed or dedicated to the County shall be dedicated to the HOA and be maintained by the same.

9. 8.-Disclosure. Prior to entering into a contract of sale, prospective purchasers shall be notified in writing by the Applicants of **the land use and parking**

restraints imposed by the proffers as well as the maintenance responsibility for the private roadways, guest parking spaces, painted walkways, stormwater management facilities, common area landscaping and any other open space amenities and shall acknowledge receipt of this information in writing. The initial deeds of conveyance and HOA governing documents shall expressly contain these disclosures.

10. ~~9.~~ Public Access Easement. At the time of record plat recordation, the Applicant shall cause to be recorded among the land records a public access easement running to the benefit of Fairfax County, in a form acceptable to the County Attorney, over the private road and sidewalks as generally shown on the CDP/FDP.

11. ~~10.~~ Escalation. All monetary contributions required by these proffers shall escalate on a yearly basis from the base year of 2012, and change effective each January 1 thereafter, based on the Consumer Price Index as published by the Bureau of Labor Statistics, the U.S. Department of Labor for the Washington-Baltimore, MD-VA-DC-WV Consolidated Metropolitan Statistical Area (the "CPI), as permitted by Virginia State Code Section 15.2-2303.3.

12. ~~11.~~ Garage Conversion. Any conversion of garages or use of garages that precludes the parking of vehicles within the garage is prohibited. **Garages shall not be converted to living space.** A covenant setting forth this restriction shall be recorded among the land records of Fairfax County in a form approved by the County Attorney prior to the sale of any lots and shall run to the benefit of the HOA and the Board of Supervisors. This restriction shall also be disclosed in the HOA documents. Prospective purchasers shall be advised of this use restriction, in writing, prior to entering into a contract of sale.

13. Parking. The parking of boats or recreational vehicles shall be prohibited within the community. This restraint shall also be described in the HOA documents and to prospective purchasers, in writing, prior to entering into a sales contract.

14. ~~12.~~ Length of Driveways. All driveways serving the residential single family units shall be a minimum of twenty feet (20') in length as measured outward from the face of the garage door to the edge of the sidewalk.

15. ~~13.~~ Lot Typical, Decks and Similar Appurtenances. Decks, bay windows, patios, chimneys, areaways, stairs and stoops, mechanical equipment and other similar appurtenances may encroach into minimum yards as depicted on the "lot typical" as shown on Sheet 3 of the CDP/FDP, as permitted by Section 2-412 and Article 10 of the Zoning Ordinance. Side yards shall be a minimum of seven (7) feet. No sheds shall be permitted in the rear yards. ~~Side yards shall be a minimum of seven (7) feet.~~ Porches (including screened in porches) or sunrooms may be permitted in the rear yard in the area identified as "Deck, Addition or Accessory Feature Area" on the lot typical included on Sheet 3 of the CDP/FDP. The specifications of this proffer shall be disclosed to future homeowners in the Homeowners Association documents.

16. Retaining Walls. The retaining walls shall be finished as to have the appearance of stone facing or brick as detailed on Sheet 16 of the CDP/FDP. Retaining wall heights and locations are subject to final engineering and approval at the time of subdivision plan approval. They may be reduced in height, or eliminated subject to final grading at the time of subdivision plan review.

II. TRANSPORTATION

17. ~~14.~~ Right-of-Way Dedication along Little River Turnpike. At the time of record plat recordation, or upon demand by VDOT or Fairfax County, whichever occurs first, the Applicant shall dedicate, at no cost to Fairfax County and in fee simple to the Board, the right-of-way along the site frontage of Little River Turnpike and any associated ancillary easements, as generally shown on the CDP/FDP.

18. ~~15.~~ Willow Run Road Frontage Improvements. Prior to the issuance of the first Residential Use Permit for the single family dwellings on the subject property, the Applicant shall construct improvements along Willow Run Drive as shown on the CDP/FDP.

19. ~~16.~~ Bus Shelter. A bus shelter along Little River Turnpike shall be provided by the Applicant in consultation with DPWES and Fairfax County Department of Transportation (FCDOT). The bus shelter shall be installed prior to issuance of the first Residential Use Permit; provided, however, that the Zoning Administrator may administratively approve a later date for completion of the improvement upon demonstration by the Applicant that despite diligent efforts and due to factors beyond the Applicant's control, the required improvements have been delayed. Final locations shall be determined in consultation with FCDOT and VDOT at the time of subdivision approval.

20. ~~17.~~ Traffic Signal Pro-Rata Contribution. Prior to the issuance of the first Residential Use Permit, the Applicant shall contribute \$2,250 to Fairfax County Board of Supervisors to be used for the traffic signal programmed for the intersection of Little River Turnpike and Willow Run Drive.

21. ~~18.~~ Private Road. The street width and remaining standards shall be designed and constructed in accordance with the private residential street standards in accordance with the PFM, subject to DPWES approval.

22. ~~19.~~ Guest Parking Spaces. Signs shall be posted that the parking spaces along the street are reserved for guests. ~~No RV's or~~ Consistent with the requirements of these proffers, no recreational vehicles (RV's), commercial vehicles, boats or trailer shall be permitted in those spaces. The restrictions that the parking spaces are restricted for guests shall be included in the initial deeds of conveyance and the HOA governing documents shall expressly contain these disclosures.

III. CONSTRUCTION

23. ~~20.~~ Construction Access and Hours. The staging and parking of construction vehicles shall occur on the Property, including personal vehicles utilized by construction workers. No parking shall occur on adjacent roadways. The hours of initial construction shall be posted in English and in Spanish and shall be limited to the hours between 7:00 a.m. and ~~97:00~~30 p.m. Monday through Friday and 8:00 a.m. to ~~97:00~~30 p.m. on Saturdays. No construction shall occur on Sundays or Federal Holidays. This shall be disclosed to all contractors and sub-contractors who perform work on the subject property during site construction.

24. ~~21.~~ Erosion & Sedimentation Controls. To ensure off-site properties are not impacted by silt or associated run-off, the Applicant shall design and implement siltation control mechanisms that shall include "super silt" fencing or similar procedures as determined by DPWES. The functioning and integrity of all erosion and sedimentation controls (E&S controls) required by DPWES shall be inspected, by the Applicant or their designated representative, no later than the next business day following

each storm event during the period of construction on-site. If the E&S controls have been damaged or breached, the E&S controls shall be repaired in accordance with the requirements of the Fairfax County Public Facilities Manual as determined by DPWES.

IV. ENVIRONMENTAL

25. 22. Stormwater Management Facilities and Best Management Practices.

Stormwater management shall be provided as generally depicted on the CDP/FDP and in accordance with Waiver #25234 WPFM-001-1, as approved by DPWES. The stormwater management techniques may include but are not limited to the following: ~~rain tanks~~ dry detention pond, rain gardens, filtera systems, infiltration trenches, drainage swales, or bay filters, ~~storm tech chamber, underground vault, or an underground detention system.~~ Stormwater management. All such facilities/Best Management Practices ("BMPs") shall be provided as generally depicted on the CDP/FDP. shall be located in a manner that is in substantial conformance with the CDP/FDP. If warranted by final engineering, minor modifications to the size, location and configuration of the dry detention pond may be made in connection with subdivision plan approval; provided however, that such changes shall not serve to diminish the effectiveness of any required screening and landscaping. Similarly, the Applicant acknowledges that such minor modifications may result in a loss of density. Adequate outfall shall be demonstrated in accordance with the PFM as determined by DPWES. If the options listed above are not approved by DPWES, a Proffered Condition Amendment or proffer interpretation will be required.

All-SWM and BMP facilities/improvements not accepted for maintenance by Fairfax County shall be properly maintained on the Property in a manner determined by DPWES. Dry detention facilities are maintained by Fairfax County. The

requirements for maintaining the ~~SWM facility~~other non-County maintained SWM improvements shall be in a standard maintenance agreement between the County and the Applicant who is the land owner, its successor and assigns. This agreement shall be recorded in the County land records and run with the land. Should any deficiencies in the existing SWM or BMP facilities/improvements be identified by the Stormwater Management Maintenance Division during regular inspections, or when investigating a drainage complaint, then maintenance shall be performed in accordance with the recorded maintenance agreement.

26. ~~23.~~ Stormwater Management and BMP Maintenance. After establishing the HOA, the Applicant shall provide the HOA and all future homeowners with written materials in the form of a manual describing the proper maintenance of ~~the~~any approved stormwater management facilities and ~~BMPs~~not otherwise maintained by Fairfax County, including the need for inspections, cleaning and general maintenance in accordance with County guidelines. ~~Consistent with the conditions for Waiver #25234 WPFM-001-1, the Applicant shall place in~~ and the manufacturer's guidelines. Should the approved subdivision plan reflect any stormwater facilities not maintained by Fairfax County, the Applicant shall establish an escrow funds for the HOA to provide for the future maintenance of such facilities/improvements as well as a contribution towards a reserve fund for the future replacement of the underground facility which will receive annual deposits from the HOA based on initial construction costs. The amount of such escrow shall be approved by DPWES.

27. ~~24.~~ Landscaping. At the time of subdivision plan review, the Applicant shall submit to DPWES, a landscape plan showing landscaping consistent with the quality, quantity and general location shown on the Landscape Plan of the CDP/FDP.

This plan shall be subject to review and approval of Urban Forestry Management, DPWES. At the time of planting, the minimum caliper for deciduous trees shall be two (2.0) inches to three (3) inches and the minimum height for evergreen trees shall be eight (8) feet. Actual types and species of vegetation shall be determined pursuant to more detailed landscape plans approved by Urban Forest Management at the time of subdivision plan approval. Maintenance responsibilities for the landscaping shall be disclosed in the homeowners' association documents.

28. ~~25.-Landscape Buffer.~~ The landscape buffer around the perimeter of the property shall be owned and maintained by the Homeowners Association. The rear of the single family lots shall be clearly defined by either a fence and/or vegetative buffer to delineate where the lot ends and the landscape buffer begins. The maintenance responsibilities of the landscape buffer shall be disclosed in HOA documents which shall be distributed to all future homeowners.

29. ~~26.-Energy Conservation.~~ All new dwelling units shall be designed and constructed as ENERGY STAR[®] qualified homes. The major features of an ENERGY STAR home include: Effective Insulation, High Performance Windows, Tight Construction and Ducts, Efficient Heating and Cooling Equipment, Efficient Products (may include but are not limited to: refrigerator, stove and dishwasher) and Third Party Verification (Home Energy Rater). Prior to issuance of the Residential use Permit (RUP) for each dwelling unit, documentation shall be submitted to the Environment and Development Review Branch of the Department of Planning and Zoning from a home energy rater certified through the Residential Energy Services network (RESNET) program that demonstrates that the dwelling unit has attained the ENERGY STAR for homes certification, as described in these conditions.

30. ~~27.~~ Interior Noise. In order to reduce interior noise to a level of approximately DNL 45 dBA, lots 1-4, ~~33~~~~27-35~~**29** within the highway noise impact zone of DNL 65-70 dBA shall employ the following acoustical treatment measures:

- Exterior walls shall have a laboratory sound transmission class (STC) rating of at least 39.
- Doors and glazing shall have a laboratory STC rating of at least 28 unless glazing constitutes more than 20 percent of any façade exposed to noise levels of DNL 65 dBA or above. If glazing constitutes more than 20 percent of an exposed façade, then the glazing shall have an STC rating of at least 39.
- All surfaces shall be sealed and caulked in accordance with methods approved by the American Society of Testing and Materials (ASTM) to minimize sound transmission.

In lieu of applying these measures, the Applicant may submit a revised noise study, based on final grading and engineering plans, prior to filing for a building permit to determine appropriate noise attenuation measures in order to reduce interior noise to a level of approximately DNL 45 dBA for lots which are within the highway noise impact zone of DNL 65-70 dBA. Noise attenuation measure may include but are not limited to appropriate STC ratings and construction for walls and windows. The noise study will be conducted by a qualified engineer and the noise attenuation measures shall be subject to review and approval of the Environmental Branch of the Department of Planning and Zoning.

31. ~~28.~~ Exterior Noise. All lots affected by highway noise above DNL 65 dBA are shown on the CDP/FDP. Exterior noise levels for outdoor recreational areas for

the lots within the DNL 65 dBA zone shall be reduced below DNL 65 dBA through the use of noise attenuation fencing as shown on the CDP/FDP. The acoustical fence shall be architecturally solid from ground up with no gaps or openings as shown on the CDP/FDP. At the time of Subdivision Plan approval, the Applicant shall have the option to submit a revised noise study based on final grading and engineering plans. The noise study will be conducted by a qualified engineer and the noise attenuation measures shall be subject to review and approval of the Environmental Branch of Department of Planning and Zoning.

V. TREE PRESERVATION

32. ~~29.~~ Tree Preservation Plan. The applicant shall submit a Tree Preservation Plan and Narrative as part of the first and all subsequent submissions of the subdivision plan review process. The preservation plan and narrative shall be prepared by a Certified Arborist or a Registered Consulting Arborist, and shall be subject to the review and approval of the Urban Forest Management Division (UFMD), DPWES.

The tree preservation plan shall include a tree inventory that identifies the location, species, critical root zone and size for all individual trees to be preserved, as well as all on and off-site trees, living or dead with trunks eight (8) inches in diameter and greater (measured at 4 1/2 -feet from the base of the trunk or as otherwise allowed in the latest edition of the Guide for Plant Appraisal published by the International Society of Arboriculture) located within 25 feet of either side of the limits of clearing and grading. Trees to be inventoried at the northeast corner of the site shall be limited to those as shown on sheet 9 of the CDP/FDP or as directed by UFMD. Additional condition analysis shall be provided for all trees inventoried. The tree preservation plan shall provide for the preservation of those areas shown for tree preservation, those areas

outside of the limits of clearing and grading shown on the CDP/FDP and those additional areas in which trees can be preserved as a result of final engineering. The tree preservation plan and narrative shall include all items specified in PFM 12-0507 and 12-0509. Specific tree preservation activities that will maximize the survivability of any tree identified to be preserved, such as: crown pruning, root pruning along the limits of clearing (LOC), mulching, fertilization, installation of welded wire tree protection fencing and others as necessary, shall be included in the plan.

33. ~~30.~~ Site Monitoring. During any clearing or tree/vegetation/structure removal on the Applicant Property, a representative of the Applicant shall be present to monitor the process and ensure that the activities are conducted as proffered and as approved by the UFMD. The Applicant shall retain the services of a certified arborist or registered consulting arborist to monitor all construction and demolition work and tree preservation efforts in order to ensure conformance with all tree preservation proffers, and UFMD approvals. The monitoring schedule shall be described and detailed in the Landscaping and Tree Preservation Plan, and reviewed and approved by the UFMD, DPWES.

34. ~~31.~~ Tree Preservation Walk-Through. The Applicant shall retain the services of a certified arborist or registered consulting arborist, and shall have the limits of clearing and grading marked with a continuous line of flagging prior to the walk-through meeting as part of the tree preservation plan. During the tree preservation walk-through meeting which shall occur prior to the commencement of construction, the Applicant's certified arborist or registered consulting arborist shall walk the limits of clearing and grading with an UFMD, DPWES, representative to determine where adjustments to the clearing limits can be made to increase the area of tree preservation

and/or to increase the survivability of trees at the edge of the limits of clearing and grading, and such adjustment shall be implemented.

Trees that are identified as dead or dying may be removed as part of the clearing operation. Any tree that is so designated shall be removed using a chain saw and such removal shall be accomplished in a manner that avoids damage to surrounding trees and associated understory vegetation. If a stump must be removed, this shall be done using a stump-grinding machine in a manner causing as little disturbance as possible to adjacent trees and associated understory vegetation and soil conditions

35. ~~32.~~ Limits of Clearing and Grading. The Applicant shall conform substantially to the limits of clearing and grading as shown on the CDP/FDP, subject to allowances specified in these proffered conditions and for the installation of utilities and/or trails as determined necessary by the Director of DPWES, as described herein. If it is determined necessary to install utilities and/or trails in areas protected by the limits of clearing and grading as shown on the CDP/FDP, they shall be located in the least disruptive manner necessary as determined by the UFMD, DPWES. A replanting plan shall be developed and implemented, subject to approval by the UFMD, DPWES, for any areas protected by the limits of clearing and grading that must be disturbed for such utilities. Any trees impacted within the limits of clearing and grading as specified above shall be replaced on the site as determined by UFMD.

36. ~~33.~~ Tree Preservation Fencing. All trees shown to be preserved on the tree preservation plan shall be protected by tree protection fence. Tree protection fencing in the form of four (4) foot high, fourteen (14) gauge welded wire attached to six (6) foot steel posts driven eighteen (18) inches into the ground and placed no further than ten (10) feet apart or, super silt fence to the extent that required trenching for super silt fence does

not sever or wound compression roots which can lead to structural failure and/or uprooting of trees shall be erected at the limits of clearing and grading as shown on the demolition, and phase I & II erosion and sediment control sheets, as may be modified by the "Root Pruning" proffer below.

All tree protection fencing shall be installed after the tree preservation walk-through meeting but prior to any clearing and grading activities, including the demolition of any existing structures. The installation of all tree protection fencing shall be performed under the supervision of a certified arborist, and accomplished in a manner that does not harm existing vegetation that is to be preserved. Three (3) days prior to the commencement of any clearing, grading or demolition activities, but subsequent to the installation of the tree protection devices, the UFMD, DPWES, shall be notified and given the opportunity to inspect the site to ensure that all tree protection devices have been correctly installed. If it is determined that the fencing has not been installed correctly, no grading or construction activities shall occur until the fencing is installed correctly, as determined by the UFMD, DPWES.

37. ~~34.~~ Root Pruning. The Applicant shall root prune after the tree preservation walk-through, as needed to comply with the tree preservation requirements of these proffers. All treatments shall be clearly identified, labeled, and detailed on the erosion and sediment control sheets of the subdivision plan submission. The details for these treatments shall be reviewed and approved by the UFMD, DPWES, accomplished in a manner that protects affected and adjacent vegetation to be preserved, and may include, but not be limited to the following:

- Root pruning shall be done with a trencher or vibratory plow to a depth of 18 inches.

- Root pruning shall take place prior to any clearing and grading, or demolition of structures.
- Root pruning shall be conducted with the supervision of a certified arborist.
- An UFMD, DPWES, representative shall be informed when all root pruning and tree protection fence installation is complete.

38. ~~35.~~ Tree Appraisal. The Applicant shall retain a professional arborist with experience in plant appraisal, to determine the replacement value of all trees 8 inches in diameter or greater located on the Application Property that are shown to be saved on the Tree Preservation Plan. These trees and their value shall be identified on the Tree Preservation Plan at the time of the first submission of the respective subdivision plan(s). The replacement value shall take into consideration the age, size and condition of these trees and shall be determined by the so-called "Trunk Formula Method" contained in the latest edition of the Guide for Plant Appraisal published by the International Society of Arboriculture, subject to review and approval by UFMD.

At the time of the respective subdivision plan approvals, the Applicant shall post a cash bond or a letter of credit payable to the County of Fairfax to ensure preservation and/or replacement of the trees for which a tree value has been determined in accordance with the paragraph above (the "Bonded Trees") that die or are dying due to unauthorized construction activities. The letter of credit or cash deposit shall be equal to 50% of the replacement value of the Bonded Trees. At any time prior to final bond release for the improvements on the Application Property constructed adjacent to the respective tree save areas, should any Bonded Trees die, be removed, or are determined to be dying by UFMD due to unauthorized construction activities, the Applicant shall replace such trees at its expense. The replacement trees shall be of equivalent size,

species and/or canopy cover as approved by UFMD. In addition to this replacement obligation, the Applicant shall also make a payment equal to the value of any Bonded Tree that is dead or dying or improperly removed due to unauthorized construction activity. This payment shall be determined based on the Trunk Formula Method and paid to a fund established by the County for furtherance of tree preservation objectives. Upon release of the bond for the improvements on the Application Property constructed adjacent to the respective tree save areas, any amount remaining in the tree bonds required by this proffer shall be returned/released to the Applicant.

39. ~~36.~~ Tree Transplant Plan. The applicant shall provide a transplantation plan as part of the first and all subsequent submissions of the subdivision plan. The plan shall be prepared by a professional with experience in the preparation of tree transplanting plans, such as a Certified Arborist or Registered Consulting Arborist. The plan as detailed on Sheet 15 of the CDP/FDP shall address all of the following items: (1) the species and sizes to be transplanted, (2) the existing locations of the trees, (3) staging location(s) (4) the proposed final locations of the trees, (5) the proposed time of year when the trees will be moved, (6) the transplant methods to be used, including tree spade size, (7) details regarding after-transplant care, including mulching, watering, soil amendments, etc., support measures such as guying or staking all subject to approval of UFMD. Note, the final location of the trees to be transplanted as shown on Sheet 14 of the CDP/FDP may be adjusted in consultation with UFM at the time of subdivision plan.

VI. STREAM RESTORATION AND INVASIVE PLANT SPECIES MANAGEMENT PLAN

40. ~~37.~~ Stream Restoration. The stream on the property shall be restored in the general location shown on the sheet entitled Conceptual Stream Restoration Plan

accompanying the CDP/FDP, subject to review and approval by DPWES and the Northern Virginia Soil and Water Conservation District (NVSWCD). HEC-RAS shall be used to determine velocities and shear stresses from the design flow rates in the channel bed and any overbank flow area. Substrate materials for the stream shall be specified based on these results. Non-erosive velocities of the substrate material in the stream channel during the 2-year storm event shall be demonstrated in the design calculations. Allowable velocities shall be based on requirement of the Public Facilities Manual (PFM) or by other accepted engineering methods as approved by DPWES. The design shall also provide incipient motion, scour, limiting slope criteria and bed armoring calculations to demonstrate the adequacy of the specified cobble size in the streambed. Calculations shall also be provided to check for toe and bank stability. Final design characteristics shall be subject to review and modification by DPWES and the NVSWCD and shall be submitted at the time of subdivision plan.

41. ~~38.~~ Invasive Plant Species Management Plan. As part of the first and all subsequent submissions of the subdivision plan review process the Applicant shall submit a Stream Restoration Plan and Invasive Plant Species Management Plan (Restoration Plan) prepared by a Certified Arborist or Registered Consulting Arborist and shall be subject to the review and approval of the Department of Public Works and Environmental Services and UFMD. The plan will:

- Establish invasive plant management success criteria for evaluation purposes. This plan will describe and document the invasive plant species present. Provide information about each identified invasive plant species. It will include monitoring objectives and protocols for measuring effectiveness of management actions.
- The plan will:
 - Prioritize management of the identified invasive plant species and provide proactive prevention and early detection/rapid response

strategies for newly invading plant species (example: assisting with education of volunteers to conduct invasive species searches and implementing management strategies).

- Describe selected management strategies and control options for invasive plant populations/infested areas, prevention, early detection, control (eradication, suppression, containment), and restoration.
 - Include the selected methods by which the management strategies are to be achieved (e.g. specific treatments such as herbicide application rate and timing, manual removal).
 - Include a list of equipment and other resources to be used in the management plan.
- Annual monitoring shall include restoration reports to DPWES to be submitted by the end of the calendar year each year for five years commencement of the restoration plan. Commencement of the restoration plan shall occur within six months of the final inspection of the landscaping plan by DPWES.

42. ~~39.~~ Outreach to Students. As part of the restoration project, outreach programs shall be offered to students within the Fairfax County School system within the school pyramid for the subject property to teach them about the restoration of the stream.

43. ~~40.~~ Stream Restoration Sign. A sign detailing that the stream has been restored shall be posted in the vicinity of the stream prior to submission of the final annual monitoring report.

VII. RECREATION

44. ~~41.~~ Park Authority Contributions: The Applicant shall contribute \$91,08675,471 to the Board of Supervisors, within 60 days after the Board of Supervisors approves this rezoning application for transfer to the Fairfax County Park Authority, for use at off-site recreational facilities intended to serve the future residents, as determined by FCPA.

45. ~~42.~~ Parks and Recreation. Pursuant to Section 6-409 of the Zoning Ordinance regarding developed recreational facilities, the Applicant shall provide the

recreational facilities to serve the Application Property. The amenity areas ~~located at the northern end and southern end of the property~~ may be programmed with recreational amenities at the discretion of the homeowners association after subdivision plan approval. The recreational amenities may include but are not limited to passive and active recreational features which may include but are not limited to: additional landscaping, playground equipment, play area, a tot lot, picnic area, gazebo, benches and street furniture. Per Section 6-409, recreational facilities such as recreational trails, walking paths, excluding any trails required by the Comprehensive Plan, and similar features shall be used to fulfill this requirement. At the time of subdivision plan review, the Applicant shall demonstrate that the value of any proposed recreational amenities are equivalent to a minimum of \$1,700 per unit (or as Section 6-409 may escalate). In the event it is demonstrated that the proposed facilities do not have sufficient value, the Applicant shall contribute funds in the amount needed to achieve the overall proffered amount of \$1,700 per unit to the Fairfax County Park Authority ("FCPA") for off-site recreational facilities intended to serve the future residents within the Mason District.

VIII. OTHER

46. ~~43. Temporary Signage.~~ No temporary signs (including "popsicle" style paper or cardboard signs) which are prohibited by Article 12 of the Zoning Ordinance, and no signs which are prohibited by Chapter 7 of Title 33.1 or Chapter 8 of Title 46.2 of the Code of Virginia shall be placed on or off-site by the Applicant or at the Applicant's direction to assist in the initial marketing and sale of homes on the subject Property. Furthermore, the Applicant shall direct its agents and employees involved in marketing and/or sale of residential units on the subject Property to adhere to this proffer.

47. ~~44.~~ School Contribution. A contribution of \$150,048~~140,670~~ (~~1615~~ students X \$9,378) shall be made to the Board of Supervisors for transfer to Fairfax County Public Schools (FCPS) and designated for capital improvements directed to the Annandale High School Pyramid and/or Cluster III schools that service the subject property. The contribution shall be made at the time of, or prior to, issuance of the first Building Permit for the approved single family detached units. Follow approval of this Application and prior to the Applicant's payment of the amount set forth in this Proffer, if Fairfax County should increase the contribution per student, the Applicant shall increase the amount of the contribution for that phase of development to reflect the then-current contribution. In addition, notification shall be given to FCPS when construction is anticipated to commence to assist FCPS by allowing for the timely projection of future students as a part of the Capital Improvement Program.

48. ~~45.~~ Affordable Dwelling Units. Prior to the issuance of the first Building Permit for the single family attached units, the Applicant shall contribute to the Fairfax County Housing Trust Fund the sum equal to one half of one percent (1/2 %) of the value of all the units approved on the property. The one half of one percent (1/2 %) contribution shall be based on the aggregate sales price of all of the units subject to the contribution, as if those units were sold at the time of the issuance of the first Building Permit. The projected sales price shall be determined by the Applicant through an evaluation of the sales prices of comparable units in the area, in consultation with the Fairfax County Department of Housing and Community Development (HCD) and DPWES.

49. ~~46.~~ Successors and Assigns. Each reference to "Applicant" in this Proffer Statement shall include within its meaning, and shall be binding upon, Applicant's

successor(s) in interest, assigns, and/or developer(s) of the Property or any portion of the Property.

Neighborhoods VI, LLC

By: _____
Name: _____
Title: _____

6651, LLC

By: _____
Name: _____
Title: _____

\\34476950.634476950.11

PROPOSED DEVELOPMENT PLAN CONDITIONS

FDP 2011-MA-029

May 31, 2012

If it is the intent of the Planning Commission to approve Final Development Plan FDP 2011-MA-029 for residential development located at Tax Maps 71-2 ((1)) 36, 71-2 ((13)) 1, and 71-2 ((10)) 17A, staff recommends that the Planning Commission condition the approval by requiring conformance with the following development conditions.

1. Development of the property shall be in substantial conformance with the Final Development Plan entitled "Callaway Conceptual/Final Development Plan RZ 2011-MA-029" prepared by BC Consultants consisting of twenty-four sheets dated July 2011, as revised through May 16, 2012.
2. The quantity and species types listed in the Proposed Tree List and Tree Canopy Calculation chart shown on Sheet 8 of the CDP/FDP may be modified provided that the 10 year tree canopy requirement is met subject to the review and approval of Urban Forest Management.

The proposed conditions are staff recommendations and do not reflect the position of the Planning Commission unless and until adopted by that Commission.

CALLAWAY

CONCEPTUAL/FINAL DEVELOPMENT PLAN

RZ-2011-MA-029

MASON DISTRICT
FAIRFAX COUNTY, VIRGINIA

JULY, 2011

REVISED AUGUST 5, 2011	REVISED FEBRUARY 17, 2012
REVISED NOVEMBER 9, 2011	REVISED MARCH 28, 2012
REVISED DECEMBER 7, 2011	REVISED APRIL 11, 2012
REVISED JANUARY 8, 2012	REVISED APRIL 30, 2012
REVISED JANUARY 30, 2012	REVISED MAY 16, 2012



VICINITY MAP
SCALE: 1" = 2,000'

CONTRACT PURCHASER/APPLICANT

NEIGHBORHOODS VI, LLC
11111 Sunset Hills Road
Suite 200
Reston, VA 20190
Telephone 703.964.5000
Fax 703.715.8076

ATTORNEY/AGENT

McGUIREWOODS, LLC
1750 Tysons Boulevard
Suite 1800
McLean, VA 22102-4215
Telephone 703.712.5000
Fax 703.712.5050

SHEET INDEX

Sheet List Table	
Sheet Number	Sheet Title
1	COVER SHEET
2	CONCEPTUAL-FINAL DEVELOPEMENT PLAN
3	GENERAL NOTES AND COMMENTS
4	EXISTING CONDITIONS AND EXISTING VEGETATION MAP
5	ILLUSTRATIVE LANDSCAPE PLAN
6	TREE CANOPY LANDSCAPE PLAN
7	CONCEPTUAL STREAM RESTORATION PLAN
8	LANDSCAPE DETAILS
9	TREE PRESERVATION PLAN
10	TREE INVENTORY AND CONDITION ANALYSIS
11	TREE INVENTORY AND CONDITION ANALYSIS
12	TREE INVENTORY AND CONDITION ANALYSIS
13	TREE PRESERVATION DETAILS
14	TREE TRANSPLANTATION PLAN
15	TREE TRANSPLANTATION SPECIFICATIONS AND DETAILS
16	AMENITY PLAN
17	ILLUSTRATIVE - ELEVATIONS
18	ILLUSTRATIVE SECTIONS
19	STREET SECTIONS AND PLANS
20	EXTENT OF REVIEW AND OUTFALL NARRATIVE
21	STORMWATER MANAGEMENT PLAN
22	STORMWATER MANAGEMENT COMPUTATIONS

ENGINEER/LANDSCAPE ARCHITECT/PLANNER

THE BC CONSULTANTS
12600 Fair Lakes Circle
Suite 100
Fairfax, VA 22033
Telephone 703.449.8100
Fax 703.449.8108


ENVIRONMENTAL AND CULTURAL RESOURCES CONSULTANT



WETLAND STUDIES AND SOLUTIONS, INC.
5300 Wellington Branch Drive
Suite 100
Gainesville, VA 20155
Telephone 703.679.5600
Fax 703.679.5601

BC Consultants
Planners • Engineers • Surveyors • Landscape Architects
12600 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)449-8100 (703)449-8108 (Fax)
www.bcconsultants.com



SHEET 1 OF 22
PROJECT # 11524-08



 EXISTING TREELINE
  PROPOSED TREELINE

APPROXIMATE LIMITS OF CLEARING AND GRADING

* APPROXIMATE LOCATION OF POSSIBLE ENTRY FEATURE/SIGN

FIELD-VERIFIED AND APPROVED RESOURCE PROTECTION AREA (23234-RPA-01-1)

PROPOSED STREET THINGS, SEE DETAIL ON SHEET 18 FOR ADDITIONAL INFORMATION

ADDITIONAL DISTURBED AREA FOR STREAM RESTORATION ONLY (PERMISSION FROM THE OWNER OF OFF-SITE RESTORATION AREA IS REQUIRED PRIOR TO ANY RESTORATION ACTIVITIES WITHIN THIS AREA)

GROSS SITE AREA (G.S.A.):	383,069 s.f. ± or 8.79405 AC. ±
EXISTING ZONE:	R-2 HC
PROPOSED ZONE:	PDH-4
PROPOSED NUMBER OF LOTS:	29
PROPOSED DENSITY:	3.30 DU/AC
OPEN SPACE REQUIRED: (20.0% OF G.S.A.):	76,613 s.f. ± OR 1.76 AC. ±
OPEN SPACE PROVIDED: (40.1% OF G.S.A.):	153,810 s.f. ± OR 3.53 AC. ±
PARKING SPACES REQUIRED:	87 (2)
PARKING SPACES PROVIDED:	149 (3)
BUILDING HEIGHT PROPOSED:	35'

- (1) TOTAL AREA TO BE REZONED, 8.79405 ACRES ±, SHOWN HEREON IS BASED ON THE MATHEMATICAL CLOSURE OF DEEDS OF RECORD AND ADJACENT INFORMATION ALL AMONG THE LAND RECORDS OF FAIRFAX COUNTY.
- (2) THREE SPACES PER UNIT FOR SINGLE FAMILY DETACHED UNITS WITH FRONTAGE ON A PRIVATE STREET.
- (3) TWO SPACES/UNIT IN THE GARAGE PLUS TWO SPACES/UNIT IN THE DRIVEWAY PLUS 33 GUEST SPACES.

BC Consultants
Planners • Engineers • Surveyors • Landscape Architects
12690 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)449-8100 (703)449-8108 (Fax)
www.bccoon.com



CONCEPTUAL/FINAL DEVELOPMENT PLAN
CONCEPTUAL-FINAL DEVELOPMENT PLAN
CALLAWAY

FAIRFAX COUNTY, VIRGINIA

REC. REVISIONS
 REVISED 08-05-11 REVISED 02-17-12
 REVISED 11-09-11 REVISED 03-28-12
 REVISED 12-07-11 REVISED 04-11-12
 REVISED 01-08-12 REVISED 04-16-12
 REVISED 01-30-12 REVISED 05-10-12
 1111 SUNSET HILLS ROAD
 NEIGHBORHOODS V. LLC
 RESTON, VA 20190

DESIGNED BY: PLR
 DRAFTED BY: CAO
 CHECKED BY: PLR
 DATE: JULY, 2011
 SCALE: HOR: 1" = 30'
 VERT:

SHEET 2 OF 22

CD. NO.
 CAD NAME: F115242FDP
 LAYOUT: FDP
 FILE NO. 11524-08

Score

1000

RAISING VEGETATION MAP LEGEND

STATEMENT (10-YEAR TREE CANOPY CALCULATIONS)

Professional Seal of Dennis D. Dixon, Landscape Architect, No. 05-16-12, State of Virginia.


BC Consultants
Planners • Engineers • Surveyors • Landscape Architects
12600 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)449-8100 (703)449-8108 (Fax)
www.bcon.com

FILE NO.	11324-08
DATE	JULY 2008
BY	WILLIAM L. HARRIS
FOR	11111 SUNSET HILLS ROAD SUITE 200 DALLAS, TEXAS 75243
REASON	REVISIONS
REVISIONS	08-05-11 REVISED 02-17-12
REVISIONS	11-09-11 REVISED 03-28-12
REVISIONS	12-07-11 04-11-12
REVISIONS	01-06-12 04-30-12
REVISIONS	01-30-12 REVISED 05-16-12

LEGEND:

- [illegible]

1
5 TREE CANOPY LANDSCAPE PLAN



CONCEPTUAL/FINAL DEVELOPMENT PLAN
ILLUSTRATIVE LANDSCAPE PLAN
CALLAWAY

MAJRON DISTRICT
FAIRFAX COUNTY, VIRGINIA



BC Consultants
Planners • Engineers • Surveyors • Landscape Architects
 2600 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
 (703)449-8100 (703)449-8108 (Fax)
www.bcon.com

DO, NO	BC REVISIONS
CAD NAME: MARIANNE LUTTREY	REVISED 06-05-11 REVISED 02-17-12
LAYOUT: ELUSTRIATION	REVISED 08-09-11 REVISED 03-30-12
FILE NO: 11924-08	REVISED 12-07-11 REVISED 04-11-12
	REVISED 01-06-12 REVISED 04-30-12
	REVISED 01-30-12 REVISED 05-16-12
SHEET 5 OF 22	APPLICANT:
	NEIGHBORHOODS V. LLC
	1111 SUNSET HILLS ROAD
	SUITE 200
	RESTON, VA 20190





TREE TYPE AND TREE CANOPY CALCULATIONS

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

TREE CANOPY CALCULATION						
DTY	TREE	SIZE	HEIGHT	USE	AREA/TREE (sq. ft.)	TOTAL CANOPY AREA (sq. ft.)
16	CATEGORY IV RECORDS TREE	7' CAL.	1.5	100	735	73,500
18	CATEGORY IV RECORDS TREE	7' CAL.	1.5	150	8,625	862,500
23	CATEGORY IV RECORDS TREE	7' CAL.	1.0	200	2,800	280,000
14	CATEGORY IV RECORDS TREE	7' CAL.	1.5	200	4,800	480,000
16	CATEGORY III RECORDS TREE	7' CAL.	1.5	150	3,000	300,000
20	CATEGORY III RECORDS TREE	7' CAL.	1.5	150	4,500	450,000
18	CATEGORY IV RECORDS TREE	7' CAL.	1.5	100	3,500	350,000
20	CATEGORY IV RECORDS TREE	7' CAL.	1.0	75	3,750	375,000
20	CATEGORY IV RECORDS TREE	7' CAL.	1.0	75	3,750	375,000
12	CATEGORY IV RECORDS TREE	10' FT.	1.0	250	3,000	300,000
21	CATEGORY IV RECORDS TREE	10' FT.	1.5	150	2,250	225,000
23	CATEGORY IV RECORDS TREE	8' FT.	1.0	200	3,800	380,000
29	CATEGORY IV RECORDS TREE	8' FT.	1.0	150	3,600	360,000
23	CATEGORY IV RECORDS TREE	8' FT.	1.0	100	3,000	300,000
26	CATEGORY IV RECORDS TREE	8' FT.	1.5	100	3,450	345,000
				SUBTOTAL		65,995 (2)
				TOTAL		65,995 (2)


2" OR 3" CAL. CATEGORY IV DECIDUOUS TREES	2" CAL. CATEGORY I-III DECIDUOUS TREES	EXISTING TREES TO BE PRESERVED (SEE SHEET 9)
<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
<input type="radio"/>	<input type="radio"/>	<input type="radio"/>

-  3rd CATEGORY 1 OCCURDENT TREES
(CONTAINING RED MAPLE SHEET TREES)
-  4th HEIGHT CATEGORY IV EXPOSED TREES
-  5th HEIGHT CATEGORY III-IV EXPOSED TREES
-  6th HEIGHT CATEGORY II EXPOSED TREES
-  7th HEIGHT CATEGORY I EXPOSED TREES
-  8th HEIGHT CATEGORY I-IV EXPOSED TREES
-  9th HEIGHT CATEGORY I-IV EXPOSED TREES
-  10th HEIGHT CATEGORY I-IV EXPOSED TREES
-  11th HEIGHT CATEGORY I-IV EXPOSED TREES
-  12th HEIGHT CATEGORY I-IV EXPOSED TREES
-  13th HEIGHT CATEGORY I-IV EXPOSED TREES
-  14th HEIGHT CATEGORY I-IV EXPOSED TREES
-  15th HEIGHT CATEGORY I-IV EXPOSED TREES
-  16th HEIGHT CATEGORY I-IV EXPOSED TREES
-  17th HEIGHT CATEGORY I-IV EXPOSED TREES
-  18th HEIGHT CATEGORY I-IV EXPOSED TREES
-  19th HEIGHT CATEGORY I-IV EXPOSED TREES
-  20th HEIGHT CATEGORY I-IV EXPOSED TREES
-  21th HEIGHT CATEGORY I-IV EXPOSED TREES
-  22th HEIGHT CATEGORY I-IV EXPOSED TREES
-  23th HEIGHT CATEGORY I-IV EXPOSED TREES
-  24th HEIGHT CATEGORY I-IV EXPOSED TREES
-  25th HEIGHT CATEGORY I-IV EXPOSED TREES
-  26th HEIGHT CATEGORY I-IV EXPOSED TREES
-  27th HEIGHT CATEGORY I-IV EXPOSED TREES
-  28th HEIGHT CATEGORY I-IV EXPOSED TREES
-  29th HEIGHT CATEGORY I-IV EXPOSED TREES
-  30th HEIGHT CATEGORY I-IV EXPOSED TREES
-  31th HEIGHT CATEGORY I-IV EXPOSED TREES
-

- 



- FSP (FOREST STEWARDSHIP PLAN) AREA (2,242 AC. ±)
 • EXCLUDE CUMULATIVE IMPACT FOR THIS TO BE MANAGED. SEE SHEET 14 FOR ADDITIONAL INFORMATION.
- RESOURCE PROTECTION AREA, RESTORATION AND ENHANCEMENT AREA
- WOULD ALSO USE THIS SET OF AREAS BASED ON TRAIL SYSTEMS TO BE DEEMED AT THE SUBDIVISION PLAN IN CONSULTATION WITH THE URBAN FOREST MANAGEMENT DIVISION.
- ADDITIONAL DESIGNATED AREA FOR STREAM RESTORATION OR A PROTECTION FOR THE OWNERS OF OFF-SITE RESTORATION AREA IS REQUIRED PRIOR TO ANY RESTORATION ACTIVITIES WITHIN THE AREA.


- [illegible]

1 TREE CANOPY LANDSCAPE PLAN
6




SCALE: 1"=50'

CONCEPTUAL/FINAL DEVELOPMENT PLAN
TREE CANOPY LANDSCAPE PLAN
CALLAWAY



BC Consultants
Planners • Engineers • Surveyors • Landscape Architects
12600 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)449-8100 (703)449-8108 (Fax)
www.becon.com

FILED	NO. 11524-08	DATE	JUL 24 2011	CITY	ST. LOUIS	STATE	MO	BY	CLERK
SHEET 6 OF 21		<p>BC REVISIONS</p> <p>DESIGNED BY: PJA DRAFTED BY: CAD CHECKED BY: PJA DATE: JULY 2011</p> <p>SCALE: 1/8" = 1'-0"</p> <p>PROJECT: NEIGHBORHOODS V. LLC 11111 SUNSET HILLS ROAD SUITE 200</p>							
CO. NO.		<p>REVISED 08-05-11</p> <p>REVISED 11-09-11</p> <p>REVISED 12-07-11</p> <p>REVISED 01-06-12</p> <p>REVISED 01-30-12</p>							
CAD NAME: PINKIE JAMES		<p>REVISED 02-17-12</p> <p>REVISED 03-28-12</p> <p>REVISED 04-11-12</p> <p>REVISED 04-30-12</p> <p>REVISED 05-18-12</p>							
LAWYER: CANNON									



PLANTING SCHEDULE					SEEDING SCHEDULE				
CONTAINER PLANTING CODE	SPECIES GROUP ¹	SPECIES ²	INDICATOR STATUS	PLANT SPACING ³	CONTAINER SIZE, RATE, AND QUANTITY ⁴ PLANTS PER ACRE	SEED PLANTING	SPECIES GROUP ¹	SPECIES ²	INDICATOR STATUS
RIPARIAN FOREST	TREE	2/20/03 P. ALABAMICUS (SA)	FACU	10'	SEE NOTE #1	7	2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
	SHRUB	2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1	8	2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
STREAM BANK	TREE	2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1	9	2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
	SHRUB	2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1	10	2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
STREAM EDGE	TREE	2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1	11	2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
	SHRUB	2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1	12	2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'
		2/20/03 P. ALABAMICUS (HAWK)	FACU	10'	SEE NOTE #1		2/20/03 M. LUTEOFLAVUS (HAWK)	REPAIR	10'

1. To be repeated and performed for all species in each of the Species Groups as specified. This information is for informational purposes only and is not intended to be used for any other purpose.

2. To be repeated and performed for all species in each of the Species Groups as specified. This information is for informational purposes only and is not intended to be used for any other purpose.

3. To be repeated and performed for all species in each of the Species Groups as specified. This information is for informational purposes only and is not intended to be used for any other purpose.

4. To be repeated and performed for all species in each of the Species Groups as specified. This information is for informational purposes only and is not intended to be used for any other purpose.

5. To be repeated and performed for all species in each of the Species Groups as specified. This information is for informational purposes only and is not intended to be used for any other purpose.

6. To be repeated and performed

TREE INVENTORY AND CONDITION ANALYSIS													
TREE KEY	BOTANICAL NAME AND OR/COMMON NAME	SIZE	*CRZ	CONDITION	CANOPY POSITION	CROWN DENSITY	AVERAGE DBH (IN)	FINAL STATUS	ACTIVITIES	PROBLEMS	COMMENTS		
		*DBH (in)	R (ft)	% ***			D (ft)						
65	Acer sp./ Maple	30	30	66--	Co-Dominate	80	50	POS	X X	One main upper branch dead/decaying; slight lean; major broken branches	Off Site		
66	Dead (Sassafras)	12	12	-				RMP			Dead		
67	Sassafras albidum/Common Sassafras	14	14	78	Co-Dominate	70	35	P	X X X	Thin; crooked leader			
68	Dead (Sassafras)	12	12	-				RMP			Dead		
69	Sassafras albidum/Common Sassafras	14	14	78	Co-Dominate	85	20	P	X X X	Slight lean; some dead branches	Co-Dominate		
70	Acer sp./ Maple	10	10	38	Co-Dominate	65	30	POS		Some broken branches; some decay; one sided	Off Site; Poor Condition		
71	Acer sp./ Maple	12-8	20	31	Co-Dominate	70	30	POS	X	One sided; major upper branches broken	Twin Stem, Off Site; Poor Condition		
72	Rubia pseudoacacia/Black Locust	20	20	72	Co-Dominate	65	30	P	X X X	Some upper broken branches			
73	Rubia pseudoacacia/Black Locust	24	24	72	Co-Dominate	60	30	P	X X X	Dead/broken upper branches			
74	Acer sp./ Maple	24	24	68	Co-Dominate	75	45	POS		One sided; some minor branches decaying	Off Site		
75	Acer sp./ Maple	24	24	78	Co-Dominate	85	30	POS		Some broken branches	Off Site		
76	Acer sp./ Maple	10-12-12-18	27	31	Co-Dominate	70	30	POS		Major branch damage; top main trunk stems leaning; vine cover; dead/decaying branches	Multi-Stem, Off Site; Poor Condition		
77	Acer sp./ Maple	18-24	30	75	Co-Dominate	85	55	POS	X	Upper broken/decaying branches	Multi-Stem, Off Site		
78	Morus alba/Common Mulberry	10	10	38	Co-Dominate	60	25	POS		Leaning; one sided; growing into 75; dead/decaying/broken branches	Off Site; Poor Condition		
79	Acer sp./ Maple	10	10	72	Co-Dominate	70	30	POS		Growing into 78; some vine cover; broken branches	Off Site		
80	Acer sp./ Maple	10	10	78	Co-Dominate	50	20	POS		Leaning; one sided; some vine cover	Off Site		
81	Quercus phellos/Willow Oak	24	18	84	Co-Dominate	75	30	POS	X X	Some broken branches	Off Site		
82	Quercus phellos/Willow Oak	24	18	72	Co-Dominate	60	20	POS		Vine cover; one sided; dead/broken branches	Off Site		
83	Melaleuca glyptostroboides/Down Redwood	30	30	81	Dominate	95	40	P	X X X	Previously pruned			
84	Quercus phellos/Willow Oak	24	24	75	Dominate	85	45	R		In traffic island; exposed/constricted roots			
85	Fagus sp./Beech	10-8	13	78	Suppressed	75	15	R		Thin; some broken branches	Twin Stem		
86	Rubia pseudoacacia/Black Locust	24	24	72	Co-Dominate	70	20	R		Some dead/broken branches	In R.O.W.		
87	Rubia pseudoacacia/Black Locust	10	10	72	Co-Dominate	65	10	R		Some dead/broken branches	In R.O.W.		
88	Rubia pseudoacacia/Black Locust	10	10	72	Co-Dominate	70	5	R		Some dead/broken branches	In R.O.W.		
89	Rubia pseudoacacia/Black Locust	14	14	72	Co-Dominate	75	10	R		Some dead/broken branches	In R.O.W.		
90	Rubia pseudoacacia/Black Locust	12	12	72	Co-Dominate	75	10	R		Some dead/broken branches			
91	Rubia pseudoacacia/Black Locust	12	12	72	Co-Dominate	70	10	R		Some dead/broken branches			
92	Rubia pseudoacacia/Black Locust	24	24	75	Co-Dominate	75	18	R		Some dead/broken branches	In R.O.W.		
93	Rubia pseudoacacia/Black Locust	10-10-10	17	78	Co-Dominate	70	25	R		Some dead/broken branches	Multi-Stem, In R.O.W.		
94	Rubia pseudoacacia/Black Locust	20	20	78	Co-Dominate	85	18	R		Some dead/broken branches	In R.O.W.		
95	Rubia pseudoacacia/Black Locust	12	12	72	Co-Dominate	65	10	R		Some dead/broken branches	In R.O.W.		
96	Rubia pseudoacacia/Black Locust	18	18	72	Co-Dominate	70	15	R		Some dead/broken branches			
97	Rubia pseudoacacia/Black Locust	28	28	75	Co-Dominate	70	25	R		Some dead/broken branches			
98	Rubia pseudoacacia/Black Locust	12-12	17	75	Co-Dominate	75	20	R		Some dead/broken branches	Twin Stem		
99	Rubia pseudoacacia/Black Locust	18	18	72	Co-Dominate	65	15	R		Some dead/broken branches			
100	Rubia pseudoacacia/Black Locust	18	18	72	Co-Dominate	75	12	R		Some dead/broken branches			
101	Rubia pseudoacacia/Black Locust	12	12	72	Co-Dominate	65	12	R		Some dead/broken branches			
102	Dead (Black Locust)	12	12	-				-					
103	Acer sp./ Maple	10	10	28	Co-Dominate	70	8	R		Spill trunk; some rot; exposed roots	Poor Condition		
104	Quercus phellos/Willow Oak	12	12	72	Co-Dominate	85	18	R		Rootball above ground; ballam rooted			
105	Juniperus virginiana/Eastern Redcedar	10	10	69	Suppressed	95	12	R		Thin at bottom/middle; some dead branches at bottom; upper stem has broken branch; some rot			
106	Juniperus virginiana/Eastern Redcedar	15	15	75	Co-Dominate	70	20	R					
107	Pinus sp./Pine	15	15	78	Co-Dominate	70	20	R					
108	Pinus sp./Pine	24	24	78	Co-Dominate	75	50	R					

TREE INVENTORY AND CONDITION ANALYSIS CONTINUED ON SHEET 11.

SEE SHEET 9 FOR THE TREE PRESERVATION PLAN AND SHEET 13 FOR THE TREE PRESERVATION DETAILS AND NARRATIVES.

NOTES:

- NO OFF-SITE TREES OR CO-OWNED TREES SHALL BE REMOVED WITHOUT THE PRIOR PERMISSION OF THE OFF-SITE OWNER(S) OR CO-OWNED(S) OF THE TREES.
- THE ADJACENT PROPERTY OWNER(S) DID NOT GRANT PERMISSION TO ACCESS THEIR PROPERTY. THE LOCATION, DIAMETER AND CONDITION ANALYSIS FOR ALL OFF-SITE TREES HAVE BEEN ESTIMATED.
- ALL TREES 8 INCHES OR GREATER IN DIAMETER WITHIN 25 FEET OF OTHER SIDE OF THE LIMITS OF CLEARING AND GRADING HAVE BEEN LISTED EXCEPT WHERE DIRECTED OTHERWISE BY THE URBAN FOREST MANAGEMENT DIVISION.
- CONDITION ANALYSIS INFORMATION HAS BEEN PROVIDED FOR ALL TREES LISTED.

LEGEND:

- PC: (POOR CONDITION, STATUS TO BE DETERMINED IN CONSULTATION WITH THE URBAN FOREST MANAGEMENT DIVISION.)
 TSD: (POTENTIAL HAZARD OR TREE OF SPECIAL CONCERN, STATUS TO BE DETERMINED IN CONSULTATION WITH THE URBAN FOREST MANAGEMENT DIVISION.)
 P: PRESERVE
 R: REMOVE
 POS: PRESERVE OFF-SITE
 RMP: REMOVE WITH PERMISSION FROM THE URBAN FOREST MANAGEMENT DIVISION. TREE IS WITHIN UNDISTURBED AREA BUT CONDITIONS WARRANT ITS REMOVAL.
 * CRZ: CRITICAL ROOT ZONE (ONE FOOT OF RADIUS FOR EVERY INCH OF TREE DIAMETER. CRZ FOR TREES WITH MULTIPLE STEMS ARE CALCULATED BASED ON THE DIAMETER OF A TREE WITH A BASAL AREA EQUIVALENT TO THE SUM OF THE BASAL AREAS FOR ALL STEMS MEASURED. CONDITION RATINGS ARE PROVIDED AS PRECAUTIONS BASED ON METHODS OUTLINED IN THE LATEST EDITION OF THE GUIDE FOR PLANT APPRAISAL PUBLISHED BY THE INTERNATIONAL SOCIETY OF ARBORICULTURE.)

TREE INVENTORY AND CONDITION ANALYSIS													
TREE KEY	BOTANICAL NAME AND OR/COMMON NAME	SIZE	*CRZ	CONDITION	CANOPY POSITION	CROWN DENSITY	AVERAGE DBH (IN)	FINAL STATUS	ACTIVITIES	PROBLEMS	COMMENTS		
		*DBH (in)	R (ft)	% ***			D (ft)						
109	Pinus sp./Pine	26	26	78	Co-Dominate	80	55	R					
110	Taxodium distichum/Bald cypress	12	12	81	Co-Dominate	80	15	R					
111	Melaleuca glyptostroboides/Down Redwood	14	14	38	Co-Dominate	85	25	P	X X X	Split trunk in the middle and lower section.	Potential hazard; well well trunk, regular condition		
112	Melaleuca glyptostroboides/Down Redwood	26	26	81	Co-Dominate	85	25	P	X X X				
113	Melaleuca glyptostroboides/Down Redwood	18	18	81	Co-Dominate	85	25	P	X X X				
114	Taxodium distichum/Bald cypress	36	36	84	Co-Dominate	85	20	P	X				
115	Melaleuca glyptostroboides/Down Redwood	24	24	81	Co-Dominate	85	25	P	X X X				
116	Melaleuca glyptostroboides/Down Redwood	30	30	81	Co-Dominate	85	25	R					
117	Taxodium distichum/Bald cypress	24	24	84	Co-Dominate	80	20	R					
118	Melaleuca glyptostroboides/Down Redwood	28	28	81	Co-Dominate	85	25	R					
119	Melaleuca glyptostroboides/Down Redwood	27	27	81	Co-Dominate	85	25	R					
120	Melaleuca glyptostroboides/Down Redwood	24	24	81	Co-Dominate	85	25	R					
121	Taxodium distichum/Bald cypress	27	27	95	Co-Dominate	80	25	R					
122	Platanus sp./London Plane Tree	24	24	81	Co-Dominate	90	30	P	X X X	Some broken branches			
123	Rubia pseudoacacia/Black Locust	24	24	89	Co-Dominate	80	25	R					
124	Ulmus sp./Elm	28	28	78	Co-Dominate	90	60	R					
125	Prunus sp./Cherry	8	8	91	Specimen	90	12	POS					Well Pruned; off site
126	Lagerströmia indica/Crape Myrtle	5-5-5	9	94	Specimen	100	20	POS					Multi-Stem; off site
127	Thuja occidentalis/White Cedar	6-6	8	81	Co-Dominate	100	12	P	X X X	Vine cover	Remove Vines, Twin Stem		
128	Thuja occidentalis/White Cedar	6-6	8	81	Co-Dominate	100	12	P	X X X	Vine cover	Remove Vines, Twin Stem		
129	Thuja occidentalis/White Cedar	6-6	8	81	Co-Dominate	100	12	P	X X X	Vine cover	Remove Vines, Twin Stem		
130	Thuja occidentalis/White Cedar	6-6	8	81	Co-Dominate	100	12	P	X X X	Vine cover	Remove Vines, Twin Stem		
131	Thuja occidentalis/White Cedar	8	8	84	Co-Dominate	100	12	P	X X X	Vine cover	Remove Vines, Single Stem		
132	Thuja occidentalis/White Cedar	6-6	8	81	Co-Dominate	100	12	P	X X X	Vine cover	Remove Vines, Twin Stem		
133	Thuja occidentalis/White Cedar	8	8	78	Co-Dominate	100	12	P	X X X	Vine cover	Remove Vines, Single With One Small Stem		
134	Thuja occidentalis/White Cedar	8-4	9	75	Co-Dominate	100	12	P	X X X		Twin Stem		
135	Pinus sp./Pine	6-6-4-3	10	72	Co-Dominate	100	12	P	X X X		Twin Stem		
136	Thuja occidentalis/White Cedar	4-4-3-3	7	72	Co-Dominate	90	10	P	X X X	Leaning; browning; lower/upper branch damage	Multi Stem		
137	Pinus strobus/White Pine	8	8	78	Co-Dominate	95	12	P	X X X	Lower branch damage; broken branches			
138	Pinus sp./Pine	3-3-3-3	6	81	Co-Dominate	100	12	R			Multi Stem		
139	Prunus sp./Cherry	10	10	69	Co-Dominate	85	20	POS		Major branch damage; exposed roots; hanging over building	Off Site		
140	Prunus sp./Cherry	8	8	75	Co-Dominate	60	20	P	X X X	Leaning; one sided; lots of dead branches; trunk damage			
141	Quercus phellos/Willow Oak	10	10	31	Co-Dominate	50	20	R		Vine covered; one sided; small cluster of branches growing up from base; dead/decaying branches	Poor Condition		
142	Cercis canadensis/Eastern Redbud	10	10	68	Co-Dominate	70	25	P		Several dead branches at the bottom; exposed roots; one sided			
143	Pinus sp./Pine	8	8	72	Co-Dominate	80	15	P	X X X	One sided; thin; slightly leaning; vine cover			
144	Picea canadensis/Norway Spruce	8	8	72	Suppressed	100	65	R		Very thin and crowded; vine cover			

CERTIFIED ARBORIST



BC Consultants
 Planners - Engineers - Surveyors - Landscape Architects
 12000 Parkside Blvd., Suite 100, Fairfax, VA 22035
 (703) 449-8100 (703) 449-8108 (Fax)
 www.bccom.com





CONCEPTUAL/FINAL DEVELOPMENT PLAN
 TREE INVENTORY AND CONDITION ANALYSIS
CALLAWAY
 MAIN STREET
 FAIRFAX COUNTY, VIRGINIA


DESIGNED BY: PLR
 DRAFTED BY: CAD
 CHECKED BY: PLR
 DATE: JULY, 2011
 SCALE: HOR.
 VERT.
 SHEET 11 OF 22
 CO. NO.
 CAD NAME: F11524TTP-RN
 LAYOUT: TTP-INVENTORY (2)
 FILE NO. 11524-08

BIC REVISIONS	
SHT ADD 1-03-	
REVISO 03-28-	
04-11-12	
REVISO 04-30-	
REVISO 05-18-	
APPLICANT	
NEIGHBORHOODS	
11111 SUNSET HWY	
SUITE 200	
RESTON, VA 20191	
DESIGNED BY: PLR	
DRAWN BY: CAD	
CHECKED BY: PLR	
DATE: JULY, 2011	
SCALE: HOR.	
VERT.	
SHEET 12 OF 22	
CO. NO.	
CAD NAME: F11524TFP-W	
LAYOUT: TFP-INVENTORY	
FILE NO. 11524-08	

- PRIOR TO ANY CONSTRUCTION ACTIVITY, ALL INDIVIDUAL TREES AND GROUPS OF TREES MARKED FOR PRESERVATION SHALL BE PROTECTED WITH TREE PROTECTION FENCING.
- TREE PROTECTION FENCING SHALL BE POSITIONED DIRECTLY IN THE ROOT PRUNING TRENCH AND BACKFILLED FOR STABILITY OR JUST OUTSIDE THE TRENCH WITHIN THE DISTURBED AREA.
- TREE PROTECTION FENCING SHALL CONSIST OF FOUR FOOT 14-GAUGE WELDED WIRE FENCE ATTACHED TO SIX FOOT TALL 4x4 POSTS DRIVEN 18 INCHES INTO THE GROUND. POSTS SHALL BE NO FURTHER THAN 10 FEET APART.
- WHERE APPROPRIATE, BASED ON UPOD AND SLOPE CONTROL PLANS, SUPER SILT FENCE MAY BE USED AS TREE PROTECTION FENCING WITH THE APPROVAL OF FAIRFAX COUNTY.
- TREE PROTECTION FENCING SHALL BE MADE CLEARLY VISIBLE TO ALL CONSTRUCTION PERSONNEL. SIGNS, IN ENGLISH AND SPANISH, WHICH STATE "TREE PRESERVATION AREA - KEEP OUT" SHALL BE INSTALLED ON TREE PROTECTION FENCING EVERY 30 FEET.
- A CERTIFIED ARBORIST SHALL MONITOR THE INSTALLATION OF TREE PROTECTION FENCING.



- PRIOR TO ANY CONSTRUCTION ACTIVITY, ALL TREES MARKED FOR PRESERVATION ALONG THE LIMITS OF CLEARING AND GRADING SHALL BE ROOT PRUNED WHERE SHOWN ON THE PLAN.
- ROOT PRUNING SHALL BE CONDUCTED USING A TRENCHEER OR VIBRATING PLOW.
- THE ROOT PRUNING TRENCH SHALL BE A MAXIMUM OF 6 INCHES WIDE AND 18-INCHES DEEP. ONCE COMPLETED, THE ROOT PRUNING TRENCH SHALL BE IMMEDIATELY BACK FILLED.
- ROOT PRUNING SHALL BE CONDUCTED UNDER THE SUPERVISION OF A CERTIFIED ARBORIST.



- SPREAD MULCH BY HAND TO A UNIFORM THICKNESS OF 4 INCHES.
- MULCH SHALL COVER AS MUCH OF THE ENTIRE CRITICAL ROOT ZONE AS POSSIBLE UP TO 10 FEET FROM THE LIMITS OF CLEARING AND GRADING.
- MULCH SHALL CONSIST OF A WOODY MATERIAL THAT HAS BEEN CHIPPED OR SHREDDED ON OTHER APPROVED MATERIAL.
- MULCH SHALL NOT TOUCH THE BASE OF THE TREE.

TREE PRESERVATION AREA KEEP OUT

NO EQUIPMENT OR MATERIALS ARE TO BE STORED OR DEPOSITED WITHIN THIS AREA. VIOLATION BY CONSTRUCTION EQUIPMENT AND PERSONNEL IS PROHIBITED.

(CONSTRUCTION COMPANY NAME)
(COMPANY CONTACT PERSON & TELEPHONE NUMBER)

PENALTY FOR VIOLATIONS
STRICTLY ENFORCED

SPECIFICATIONS:

ONE-SIDED: WIDTH: 17 INCHES MINIMUM
HEIGHT: 11 INCHES MINIMUM
BACKGROUND COLOR: WHITE
LETTER COLOR: BLACK
LETTER SIZE: 1.5 INCH MINIMUM (LARGEST)
LETTER 2: 0.75 INCH MINIMUM
LETTER 3: 0.5 INCH MINIMUM
LETTER 4: 0.375 INCH MINIMUM (SMALLEST)
LANGUAGE: ENGLISH AND SPANISH (SEPARATE SIGNS)

NOTE: A TYPED SIGNATURE MAY BE SUBMITTED TO FAIRFAX COUNTY FOR APPROVAL.

TREE PRESERVATION SIGN

13 NOT TO SCALE 1/31/2008 Tree Protection

TREE PROTECTION FENCE

13 NOT TO SCALE 1/31/2008 Tree Protection

PROTECTIVE MULCHING

13 NOT TO SCALE 1/31/2008 Tree Protection

SITE MONITORING SCHEDULE

LIST OF DUTIES	DATE	DESCRIPTION OF DUTIES
PRE-CONSTRUCTION MEETING IN FIELD TO WALK-LIMITS OF CLEARING AND GRADING	SPECIFIED BY UPOD	TREE PRESERVATION WALK-THROUGH: THE APPLICANT SHALL RETAIN THE SERVICES OF A CERTIFIED ARBORIST OR A REGISTERED CONSULTING ARBORIST, AND SHALL HAVE THE LIMITS OF CLEARING AND GRADING MARKED WITH A CONTINUOUS LINE OF FLAGGING PRIOR TO THE WALK-THROUGH MEETING. DURING THE TREE-PRESERVATION WALK-THROUGH MEETING, THE APPLICANT'S CERTIFIED ARBORIST OR LANDSCAPE ARCHITECT SHALL WALK THE LIMITS OF CLEARING AND GRADING WITH AN UPOD, DPWES, REPRESENTATIVE TO DETERMINE WHERE ADJUSTMENTS TO THE CLEARING LIMITS CAN BE MADE TO INCREASE THE AREA OF TREE PRESERVATION AND/OR INCREASE THE SURVIVABILITY OF TREES AT THE EDGE OF THE LIMITS OF CLEARING AND GRADING, AND SUCH ADJUSTMENTS SHALL BE IMPLEMENTED. TREES THAT ARE IDENTIFIED AS DEAD OR DYING MAY BE REMOVED AS PART OF THE CLEARING OPERATION. ANY TREE THAT IS SO DESIGNATED SHALL BE REMOVED USING A CHAIN SAW AND SUCH REMOVAL SHALL BE ACCOMPLISHED IN A MANNER THAT AVOIDS DAMAGE TO SURROUNDING TREES AND ASSOCIATED UNDERSTORY VEGETATION. IF A STUMP MUST BE REMOVED, THIS SHALL BE DONE USING A STUMP-GRINDING MACHINE IN A MANNER CAUSING AS LITTLE DISTURBANCE AS POSSIBLE TO ADJACENT TREES AND ASSOCIATED UNDERSTORY VEGETATION AND SOIL CONDITIONS.
INSTALLATION OF TREE PROTECTION FENCE	AFTER UPOD'S APPROVAL OF LOCATION	ALL TREE PROTECTION FENCING SHALL BE INSTALLED AFTER THE TREE PRESERVATION WALK-THROUGH MEETING BUT PRIOR TO ANY CLEARING AND GRADING ACTIVITIES, INCLUDING THE DEMOLITION OF ANY EXISTING STRUCTURES. THE INSTALLATION OF ALL TREE PROTECTION FENCING SHALL BE PERFORMED UNDER THE SUPERVISION OF A CERTIFIED ARBORIST, AND ACCOMPLISHED IN A MANNER THAT DOES NOT HARM EXISTING VEGETATION THAT IS TO BE PRESERVED. THREE (3) DAYS PRIOR TO THE COMMENCEMENT OF ANY CLEARING, GRADING, OR DEMOLITION ACTIVITIES, BUT SUBSEQUENT TO THE INSTALLATION OF THE TREE PROTECTION DEVICES, THE UPOD, DPWES, SHALL BE NOTIFIED AND GIVEN THE OPPORTUNITY TO INSPECT THE SITE TO ENSURE THAT ALL TREE PROTECTION FENCING DEVICES HAVE BEEN CORRECTLY INSTALLED. IF IT IS DETERMINED THAT THE FENCING HAS NOT BEEN INSTALLED CORRECTLY, NO GRADING OR CONSTRUCTION ACTIVITIES SHALL OCCUR UNTIL THE FENCING IS INSTALLED CORRECTLY, AS DETERMINED BY THE UPOD, DPWES.
CONSTRUCTION / SITE ANALYSIS	MONTHLY ANALYSIS OF SITE OR AS SPECIFIED BY UPOD	THE APPLICANT SHALL ACTIVELY MONITOR THE SITE TO ENSURE THAT INAPPROPRIATE ACTIVITIES SUCH AS THE STORAGE OF CONSTRUCTION MATERIALS, DUMPING OF CONSTRUCTION DEBRIS, AND TRAFFIC BY CONSTRUCTION EQUIPMENT AND PERSONNEL DO NOT OCCUR WITHIN THESE AREAS.

INVASIVE SPECIES ASSESSMENT AND MANAGEMENT NARRATIVE:

INVASIVE SPECIES ASSESSMENT:

IN COVER TYPE 3, AREAS OF BRIARS, VINES AND MULTIFLORA ROSE ARE PRESENT IN THE FOREST UNDERSTORY OR AS INDIVIDUAL STANDS. IT DOES NOT APPEAR THAT THESE INVASIVE PLANTS HAVE ACHIEVED A LEVEL THAT WOULD ENDANGER THE LONG-TERM HEALTH OF THE FORESTED AREAS TO BE PRESERVED. IN SOME AREAS VINES HAVE CLIMBED THE TRUNKS OF TREES AND ARE BEGINNING TO IMPACT THE CROWNS OF THE TREES.

INVASIVE SPECIES MANAGEMENT:

CLIMBING VINES MAY HAVE A NEGATIVE IMPACT TO EXISTING TREES IF ALLOWED TO GROW INTO THE CANOPY OF PRESERVED TREES. AS PART OF THE INITIAL TREE PRESERVATION WORK, A 4' SECTION OF VINES THAT IMPACTS ROOTS, TRUNKS OR CANOPY SHALL BE REMOVED FROM PRESERVED TREES WITHIN THE ABOVE NOTED COVER TYPE. CARE SHALL BE TAKEN TO NOT DAMAGE TREE TRUNKS, ROOTS OR BARK. VINES IN THE TREE CANOPY THAT ARE NOT EASILY REMOVED SHOULD BE LEFT IN PLACE TO DIE AND FALL OUT NATURALLY. BRIARS, ADDITIONAL VINES, MULTIFLORA ROSE AND OTHER INVASIVE AND NON-NATIVE PLANT SPECIES SHOULD BE REMOVED MANUALLY OR GRADICATED CHEMICALLY. A LONG TERM INVASIVE AND NON-NATIVE PLANT SPECIES MANAGEMENT PLAN SHOULD BE DEVELOPED AND IMPLEMENTED ANNUALLY BY THE COMMUNITY'S HOMEOWNERS ASSOCIATION.

CERTIFIED ARBORIST



International Society of Arboriculture
CERTIFIED ARBORIST
Dennis Dale Dixon

Company Address: 564-0975
E-mail: dixon@isa.org
Date: 31/2011

CONCEPTUAL/FINAL DEVELOPMENT PLAN

TREE PRESERVATION DETAILS

CALLAWAY

MAKIN INTEREST
FAIRFAX COUNTY, VIRGINIA

REVISIONS

NO.	DATE	DESCRIPTION
1	02-17-12	REVISED 02-17-12
2	03-26-12	REVISED 03-26-12
3	04-10-12	REVISED 04-10-12
4	05-18-12	REVISED 05-18-12
5	06-18-12	REVISED 06-18-12
6	07-18-12	REVISED 07-18-12
7	08-18-12	REVISED 08-18-12
8	09-18-12	REVISED 09-18-12
9	10-18-12	REVISED 10-18-12
10	11-18-12	REVISED 11-18-12
11	12-18-12	REVISED 12-18-12
12	01-18-13	REVISED 01-18-13
13	02-18-13	REVISED 02-18-13
14	03-18-13	REVISED 03-18-13
15	04-18-13	REVISED 04-18-13
16	05-18-13	REVISED 05-18-13
17	06-18-13	REVISED 06-18-13
18	07-18-13	REVISED 07-18-13
19	08-18-13	REVISED 08-18-13
20	09-18-13	REVISED 09-18-13
21	10-18-13	REVISED 10-18-13
22	11-18-13	REVISED 11-18-13
23	12-18-13	REVISED 12-18-13
24	01-18-14	REVISED 01-18-14
25	02-18-14	REVISED 02-18-14
26	03-18-14	REVISED 03-18-14
27	04-18-14	REVISED 04-18-14
28	05-18-14	REVISED 05-18-14
29	06-18-14	REVISED 06-18-14
30	07-18-14	REVISED 07-18-14
31	08-18-14	REVISED 08-18-14
32	09-18-14	REVISED 09-18-14
33	10-18-14	REVISED 10-18-14
34	11-18-14	REVISED 11-18-14
35	12-18-14	REVISED 12-18-14
36	01-18-15	REVISED 01-18-15
37	02-18-15	REVISED 02-18-15
38	03-18-15	REVISED 03-18-15
39	04-18-15	REVISED 04-18-15
40	05-18-15	REVISED 05-18-15
41	06-18-15	REVISED 06-18-15
42	07-18-15	REVISED 07-18-15
43	08-18-15	REVISED 08-18-15
44	09-18-15	REVISED 09-18-15
45	10-18-15	REVISED 10-18-15
46	11-18-15	REVISED 11-18-15
47	12-18-15	REVISED 12-18-15
48	01-18-16	REVISED 01-18-16
49	02-18-16	REVISED 02-18-16
50	03-18-16	REVISED 03-18-16
51	04-18-16	REVISED 04-18-16
52	05-18-16	REVISED 05-18-16
53	06-18-16	REVISED 06-18-16
54	07-18-16	REVISED 07-18-16
55	08-18-16	REVISED 08-18-16
56	09-18-16	REVISED 09-18-16
57	10-18-16	REVISED 10-18-16
58	11-18-16	REVISED 11-18-16
59	12-18-16	REVISED 12-18-16
60	01-18-17	REVISED 01-18-17
61	02-18-17	REVISED 02-18-17
62	03-18-17	REVISED 03-18-17
63	04-18-17	REVISED 04-18-17
64	05-18-17	REVISED 05-18-17
65	06-18-17	REVISED 06-18-17
66	07-18-17	REVISED 07-18-17
67	08-18-17	REVISED 08-18-17
68	09-18-17	REVISED 09-18-17
69	10-18-17	REVISED 10-18-17
70	11-18-17	REVISED 11-18-17
71	12-18-17	REVISED 12-18-17
72	01-18-18	REVISED 01-18-18
73	02-18-18	REVISED 02-18-18
74	03-18-18	REVISED 03-18-18
75	04-18-18	REVISED 04-18-18
76	05-18-18	REVISED 05-18-18
77	06-18-18	REVISED 06-18-18
78	07-18-18	REVISED 07-18-18
79	08-18-18	REVISED 08-18-18
80	09-18-18	REVISED 09-18-18
81	10-18-18	REVISED 10-18-18
82	11-18-18	REVISED 11-18-18
83	12-18-18	REVISED 12-18-18
84	01-18-19	REVISED 01-18-19
85	02-18-19	REVISED 02-18-19
86	03-18-19	REVISED 03-18-19
87	04-18-19	REVISED 04-18-19
88	05-18-19	REVISED 05-18-19
89	06-18-19	REVISED 06-18-19
90	07-18-19	REVISED 07-18-19
91	08-18-19	REVISED 08-18-19
92	09-18-19	REVISED 09-18-19
93	10-18-19	REVISED 10-18-19
94	11-18-19	REVISED 11-18-19
95	12-18-19	REVISED 12-18-19
96	01-18-20	REVISED 01-18-20
97	02-18-20	REVISED 02-18-20
98	03-18-20	REVISED 03-18-20
99	04-18-20	REVISED 04-18-20
100	05-18-20	REVISED 05-18-20

DESIGNED BY: PJD
GRADED BY: PJD
CHECKED BY: PJD
DATE: JULY, 2011
SCALE: N/A
M/S

SHEET 13 OF 22

CO. NO.

CAD NAME: F11524TTP

LAYOUT: TTP-DETAILS

FILE NO. 11524-08



TREE TRANSPLANTATION LIST:

[illegible]

* DANGER OF TREES MANEUVERED AT 12 FEET ABOVE GROUND LINE.

** LOSS OF ANY TREE CANDIDY PROVIDED THROUGH TRANSPIRATION WILL BE RECOVERED BY THE PLANTING OF THREE PROVISIONAL TREES. CANDIDY IN CONSULTATION WITH THE URBAN FOREST MANAGEMENT DIVISION. NO BONDS WILL BE REQUIRED FOR THE TREE CANDY FOR ANY OF THE TRANSPIRATED TREES.

Received 27 June 2007
Accepted 27 June 2007
DOI: 10.1002/for

[illegible]

CONCEPTUAL/FINAL DEVELOPMENT PLAN
TREE TRANSPLANTATION PLAN
CALLAWAY
MARION DISTRICT
FAIRFAX COUNTY, VIRGINIA



BC Consultants
Planners • Engineers • Surveyors • Landscape Architects
12600 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)449-8100 (703)449-8108 (Fax)
www.bcecon.com

TREE TRANSPLANTATION SPECIFICATIONS:

1. THE CONTRACTOR SHALL SUBMIT FOR APPROVAL THE NAME AND BACKGROUND MATERIALS OF A QUALIFIED TRANSPLANT SUBCONTRACTOR WHO IS A LICENSED ARBORIST (INTERNATIONAL SOCIETY OF ARBORICULTURE OR EQUIVALENT) WITH DEMONSTRATED EXPERIENCE IN MOVING LARGE TREES, PARTICULARLY THOSE 8 INCHES IN DIAMETER BREAST HEIGHT (DBH) AND GREATER. THE SAME SUBCONTRACTOR SHALL PREPARE A DETAILED TRANSPORTATION PLAN FOR MOVING THE EXISTING TREES AS CALLED FOR IN THIS PLAN. THE CONTRACTOR'S TRANSPORTATION PLAN SHALL DESCRIBE AND/OR ILLUSTRATE IN DETAIL THE FOLLOWING:
 - 1.1 THE METHOD OF PREPARING THE TREES FOR TRANSPORT, INCLUDING ROOT PRUNING (WHICH MAY BE CALLED FOR BY THE METHOD OF TRANSPORTATION)
 - 1.2 THE METHOD OF CONTAINING ROOT BALLS FOR VARIOUS SIZES OF TREES
 - 1.3 THE PROPOSED HOISTING AND LIFTING METHODS FOR EACH SIZE CATEGORY OF TREE
 - 1.4 THE EQUIPMENT PROPOSED TO MOVE THE TREES, AND ITS ROUTING ON THE SITE FOR ALL ASPECTS OF THE OPERATION
 - 1.5 THE SCHEDULE OF WORK RELATED TO THE TRANSPORTATION OF TREES
 - 1.7 ANY OTHER DETAILS SUGGESTIONS WHICH VARY FROM THE METHODS DESCRIBED IN THIS SECTION

UPON APPROVAL BY THE REGISTERED LANDSCAPE ARCHITECT (R/LA), THE CONTRACTOR SHALL ENGAGE THE SERVICES OF THE APPROVED TRANSPLANT SUBCONTRACTOR TO PERFORM THE WORK WITH THE R/LA AND ANY APPROPRIATE AGENCY'S REPRESENTATIVES PRESENT TO PROCEEDING FURTHER WITH ANY WORK. ALL SUBSEQUENT WORK UNDER THIS SECTION SHALL BE DONE ONLY BY OR UNDER THE DIRECTION OF THE APPROVED TRANSPLANT SUBCONTRACTOR.

2. SEASON
 - 2.1 TRANSPLANTING OPERATIONS SHALL OCCUR WHEN THE GROUND IS NOT FROZEN OR OTHERWISE IN AN UNSATISFACTORY CONDITION FOR WORKING, AFTER LEAF FALL AND BEFORE BUD BREAK ON DECIDUOUS TREES. THIS SHALL BE OCTOBER 15TH TO DECEMBER 1ST OR MARCH 1ST TO APRIL 15 UNLESS OTHERWISE DIRECTED BY THE R/LA.
3. CONTACT LOSS UTILITY TO LOCATE ANY UNDERGROUND LINES IN THE AREA. ALSO MAKE WHETHER THERE ARE ANY OVERHEAD UTILITIES THAT MIGHT INTERFERE WITH THE TREE MOVING EQUIPMENT.

4. MATERIALS
 - 4.1 BURLAP AND TWINE SHALL BE NATURAL FIBER, NO SYNTHETIC BURLAP OR TWINE SHALL BE PERMITTED.
 - 4.2 PLANTING MATERIALS: TOPSOIL, WASHED SAND, SWEETWOOD HARKNESS, ANTI-CORROSION, WOOD, HOLE, TWINE, LANDSCAPE DEVELOPMENT MATERIALS AND WATER.
 - 4.3 HYDROLYSAL FERTILIZER: THIS MATERIAL SHALL BE A FINE GRANULAR PRODUCT SUPPLIED IN PLASTIC BAGS (EACH CONTAINING 3 GALLONS OF PRODUCT). THIS PRODUCT SHALL NOT BE STORED FOR MORE THAN EIGHTEEN MONTHS FOLLOWING PRODUCTION AND SHALL NOT BE EXPOSED TO HUMIDITY, DIRECT SUNLIGHT, OR TO TEMPERATURES HIGHER THAN 90 DEGREES FAHRENHEIT OR LOWER THAN 32 DEGREES FAHRENHEIT PRIOR TO INCORPORATION INTO THE SOIL. EACH BAG/PACKET SHALL CONTAIN THE FOLLOWING:
 - 4.3.1 A MINIMUM OF 1,000 LBS. SPACES OF VEGGICARE-AMBIOLUX (HYDROLYSAL FERTILIZER) INCLUDING EPHEDRAPHORUS COLUBARIANA, GLYCOLIC ACID, ETHANOLIC ACID, GLYCOLIC ACID, AND GLYCOLIC ACID.
 - 4.3.2 A MINIMUM OF 500 LBS. LIVE SPACES OF EPHEDRAPHORUS COLUBARIANA, GLYCOLIC ACID, ETHANOLIC ACID, GLYCOLIC ACID, AND GLYCOLIC ACID.
 - 4.3.3 ACRYLAMIC ACID, COPOLYMER WATER ADSORBENT GEL.
 - 4.3.4 WATER SOLUBLE DRIED RICINUS SCHODDUS EXTRACT.
 - 4.3.5 WATER SOLUBLE ACRYLAMIC ACID (SOLUBLE GEL) EXTRACT.
 - 4.3.6 WATER SOLUBLE DRIED LEMNACA MINOR (SOLUBLE GEL) EXTRACT.

- 4.4 SOIL AMENDMENT: A SOIL TEST SHALL BE CONDUCTED AND THE SOIL MAY BE AMENDED BASED ON SOIL TESTING RESULTS. SOIL AMENDMENT SHALL BE SPECIFIED ON THE PLANT SPECIFICATION.
5. STORAGE
 - 5.1 IF PLANTS ARE NOT TO BE REPLANTED IMMEDIATELY, SPECIAL STORAGE CONDITIONS ARE REQUIRED. THE PROPERLY BALLED PLANTS SHALL BE STORED IN AN AREA WITH GOOD SURFACE DRAINAGE AND COVERED WITH LOOSE, DAMP MEDIUM TO HELP KEEP THE ROOT BALL MOIST. SUCH AS COMPOSTED MUD OR SANDGUT. DUE TO THE DECOMPOSITION OF THESE MEDIUM, PROTECTIONS MUST BE MADE FOR MEDICAL MATERIALS, FUEL AND OTHER TEMPERATURES IN THE MEDIUM APPROACH TO SUCCESS. FOR LONG TERM STORAGE, PARTIAL SHADE AND AN APPROVED IRRIGATION SYSTEM IS REQUIRED.

6. GROUND AND PLANT PREPARATION
 - 6.1 ALL CUSTOMARY GOOD TRADE PRACTICE SHALL BE TAKEN IN PREPARING PLANTS FOR MOVING. WORKMANSHIP THAT FAILS TO MEET THE HIGHEST STANDARDS IS REJECTED.
 - 6.2 PRIOR TO TRANSPORTATION, EACH TREE SHALL BE MALCHED IN A CIRCLE EXTENDING 4-6 FEET FROM THE TRUNK. "GATOR BAIT" SHALL BE PLACED AROUND THE TRUNKS OF EACH TREE TO PROVIDE AT LEAST 1 INCH OF WATER PER WEEK. THE ENTIRE HOLDING AREA SHALL BE ENCLOSED WITH A TREE PROTECTION FENCING (SEE DETAIL SHEET 1/13). TREES SHALL NOT BE DISTURBED UNTIL THEY ARE TO BE MOVED TO THEIR FINAL TRANSPORT LOCATION.
 - 6.3 MARKING ORIENTATION OF TREES PRIOR TO PLANTING: THE CONTRACTOR SHALL PLACE A FLAG OF CLOTH OR PLASTIC HOOK TO A BRANCH TO MARK THE NORTH SIDE OF THE PLANT AT A QUOTE FOR POSITIONING THE PLANT IN THE NEW LOCATION. ROOT PRUNING FOR PLANTS 8 INCHES DBH OR GREATER, AT LEAST 6 MONTHS PRIOR TO TRANSPORT, AND ONLY DURING THE APPROVED SEASONS AS DESCRIBED HEREIN. THE CONTRACTOR SHALL DELINEATE, WITH CHALK, STAKE AND TWINE OR OTHER APPROVED MEANS, A CIRCLE AROUND EACH TREE, THE APPROVED LIMIT OF THE ANTICIPATED ROOT BALL. THE CIRCLE SHALL BE SHOWN WITH 3 EQUAL LENGTH STRIPS. THE CONTRACTOR SHALL, IN EVERY OTHER SECTION OF THE PERIMETER (A TOTAL OF FOUR), EXCAVATE A CIRCULAR MEDIAN 3 FEET DEEP, EXTENDING FROM 4 INCHES LESS THAN THE ROOT BALL PERIMETER TO 3 FEET BEYOND THE PERIMETER, BY A 1/2 FOOT DEEP, SETTING ASIDE THE TOPSOIL AND SUBSOIL. IN EACH OF THESE SECTIONS, ALL EXPOSED ROOTS SHALL BE BRUSHED TO GRADE AT THE VERGE OF THE EXCAVATION BY AN APPROVED MEANS WITH CLEAR, SHARP TOOLS, TO PROMOTE CALLUS FORMATION AND REDUCE CLIPPING.
 - 6.5 ROOTBALL SIZE, SEE 7/1.
 - 6.6 STAKE PLANT LAYOUT FOR ADJUSTMENTS AND APPROVAL PRIOR TO TRANSPORTING OPERATIONS BASED UPON THE OWNER'S ACCEPTED SCHEDULE AND METHODS.
 - 6.7 CROWN PRUNING: DEAD BRANCHED OR DISEASED MOULD BE REMOVED IN ACCORDANCE WITH GOOD HORTICULTURAL PRACTICE. ADDITIONAL PRUNING MAY BE REQUIRED AS DETERMINED BY THE TRANSPORTING SUBCONTRACTOR TO PRESERVE AESTHETIC BALANCE. ANY PRUNING SHALL PRESERVE THE NATURAL CHARACTER OF EACH PLANT AND SHALL BE DONE IN A MANNER APPROPRIATE TO ITS PARTICULAR CHARACTERISTICS. ANY CROWN PRUNING SHALL BE DONE DURING THE TRANSPORTING SEASON, OR PRIOR TO TRANSPORT, EITHER BEFORE OR AFTER TRANSPORTING. THE CONTRACTOR'S DISCRETION, IF DONE BEFORE, ADDITIONAL PRUNING MAY BE REQUIRED TO CORRECT ANY DAMAGE INCURRED DURING THE TRANSPORTING OPERATION. IN NO CASE SHALL LEADER BRANCHES BE REMOVED OR LAMINATED.
 - 6.8 TREES, IF NECESSARY, TO FACILITATE POSITIONING OF EQUIPMENT AND HELP AVOID HARM TO THE TREE, TRUNK OR BRANCHES OF LOW BRANCHED PLANTS LONG HEAVY TRUNK OR BULBULAR STRIPS IS ALLOWABLE, IF APPROVED IN ADVANCE BY THE R/LA. EACH POINT OF CONTACT OF TWINE OR TRUNK STRIPS OR BRANCHES SHALL BE PROTECTED WITH BURLAP.

- 6.9 TRANSPORT LOCATION: THE NEW LOCATIONS TO RECEIVE TRANSPORTS SHALL BE STAKED OUT FOR APPROVAL PRIOR TO DOING THE TREES. IN ALL CASES, THESE PITS SHALL BE DOED AND PREPARED PRIOR TO COMPLETION OF FINAL DOING OF THE TRANSPORT TREES. PITS SHALL BE THOROUGHLY WATERED ON THE DAY OF TRANSPORTING PRIOR TO RECEIVING PLANTS.
- 6.10 THE EXCAVATED SUBSOIL AND TOPSOIL SHALL BE SET ASIDE IN SEPARATE STOCKPILE FOR REUSE IN BACKFILLING. WHERE THE DEPTH OF THE EXC. THE SUBGRADE MATERIAL IS UNSATISFACTORY, IT SHALL BE REMOVED AND REPLACED WITH ADEQUATE SUBGRADE MATERIAL AND TOPSOIL.
- 6.12 WHERE A TREE SPACE IS NOT USED, THE DIAMETER SHALL BE OF 2 FEET GREATER THE DIAMETER OF THE ROOT BALL. DEPTH SHALL BE SUFFICIENT TO ENSURE THAT THE ROOT BALL WILL SET IN ITS NEW LOCATION ON UNDISTURBED SOIL, SUCH THAT THE SURFACE OF THE ROOT BALL WILL BEAT THE EXACT RELATIONSHIP TO ADJACENT NEW FINISH GRADES AS IT DOES ITS ORIGINAL LOCATION.

7. TRANSPLANT OPERATION
 - 7.1 ROOT BALLS: IN ALL CASES, THE DIAMETER OF THE BALL OF NATIVE SOIL TO BE PRESERVED INTACT SHALL BE AT LEAST 10 TIMES THE DIAMETER OF THE TREE TRUNK AT BREAST HEIGHT (DBH) UNLESS OTHERWISE APPROVED BY THE R/LA. THE DEPTH OF THE ROOT BALL SHALL BE SUFFICIENT TO PRESERVE THE MAJORITY OF LARGE ROOTS CHARACTERISTIC OF THE GIVEN TREE GROWING IN THAT PARTICULAR SOIL TYPE AS DETERMINED BY THE APPROVED TRANSPORTING SUBCONTRACTOR IN CONSULTATION WITH THE R/LA. UNLESS OTHERWISE SPECIFIED, THE DEPTH SHALL BE APPROXIMATELY 80% OF THE BALL WIDTH FOR ROOT BALLS UP TO 8 FEET AND A MINIMUM OF 4 FEET FOR ROOT BALLS GREATER THAN 8 FEET IN DIAMETER.

- 7.2 PRECAUTION: EXPOSED ROOTS SHALL NEVER BE ALLOWED TO DRY OUT. IF FOR ANY REASON THE PLANT WILL NOT BE MOVED ON THE DAY OF THE OPERATION, ROOTS SHALL BE PROTECTED BY FLOODING THEM IN MOIST STRAW, SPAGNUM, PEAT MOSS, BARK OR OTHER SUITABLE MATERIAL, AND THEN WRAP WITH MOIST BURLAP.
- 7.3 WHEN A TREE SPACE IS USED:
 - 7.3.1 USE A TREE SPACE THAT IS IN GOOD CONJUNCTION WITH A SUITABLE STAKE (MAX. 2") BETWEEN CUTTING BLADES. ALL BLADES SHALL BE TRUE TO THEIR DESIGNED SHAPE AND FREE OF BENDING, WHICH COULD INTERFERE WITH THEIR OPERATION. MOUNT TREE SPACE IN A SUFFICIENTLY STABLE MEDIUM CAPABLE OF SUPPORTING THE WEIGHT OF ALL REMOVED MATERIALS AND THEIR LOADS TO BE MOVED, THE BLADES INTO THE SOIL.
 - 7.3.2 AT THE TIME OF TRANSPORTATION, THE LOWER BRANCHES OF EACH TREE SHALL BE CAREFULLY TIED BACK AS REQUIRED TO PROVIDE A 3" VERTICAL CLEARANCE FOR THE TREE SPACE. A TREE SPACE OF NO LESS THAN 82 INCHES SHALL BE USED.
 - 7.3.3 THE APPROVED DESTINATION HOLE SHALL FIRST BE EXCAVATED IF IT IS ASSUMED THAT THIS SHALL BE THE SAME SPACE TO BE USED TO MOVE THE TREE AND THOROUGHLY WATERED.
 - 7.3.4 CUT AND REMOVE ALL WILDS AND UNDERGROW FROM TRUNKS AND BRANCHES OF TREE TO FACILITATE ACCESS BY THE TREE SPACE.
 - 7.3.5 DO NOT EXCAVATE TREE PITS MORE THAN 24 HOURS PRIOR TO PLANTING. ALL TREES MUST BE PRUNED AND THINNING MUST BE COMPLETED WITHIN 24 HOURS OF THE TIME OF PLANTING. THE PRESENT OF ALL BRANCHES BEFORE DOING BUT NO MORE THAN 20 PERCENT. DO NOT INCONSPICUOUSLY CUT BRANCHES TO BE PRUNED. THE PERCENTAGE SHALL BE HEAVY GROWN TO FORCE THE BLADES INTO THE SOIL.
 - 7.3.6 CROSSED BRANCHES: EACH TREE SHALL BE PLANTER PRUNED AT 2 WEEK INTERVALS TO REMOVED NEW SHOOTS OF THE BARK.
 - 7.3.7 EACH TREE SHALL BE CAREFULLY MOVED TO A HOLDING AREA ON SITE. THE TREE TRUNK SHALL BE PROTECTED AS NECESSARY WITH BURLAP OR PROTECTIVE PADDING (SEE DETAIL SHEET 2/13). THE SPACE/TREES WILL BE PLACED IN THE HOLES WITH THE ROOT BALL OVER ON 2-3" ABOVE THE EXISTING GRADE IN A MINIMUM 1.5 FOOT WIDE EXTENDING FROM THE EDGE OF THE ROOT BALL. THE TOP 8 INCHES OF SOIL SHALL BE LOOSELY, HYDROLYSAL FERTILIZER SHALL BE EVENLY SPREAD IN THIS ZONE AT THE RATE OF ONE POUND PER 8 SQUARE FEET AND THOROUGHLY INCORPORATED INTO THE LOOSENED LAYER.
 - 7.3.8 AFTER THE TREE IS PLACED IN THE HOLDING SPACE OR AIR PROTECTS BETWEEN THE HOLE AND THE ROOT BALL SHALL BE IMMEDIATELY FILLED IN WITH SAND "WASHED" INTO THE SPACES. ALL AIR PROTECTS MUST BE FILLED WITH THE SAND. ALL TREES SHALL BE MALCHED AND HAVE A "GATOR BAIT" INSTALLED ON AN APPROVED MEANS OF PROTECTION.

- 7.3.9 PROVIDE PERIODIC WATERING AND MISTING OF WASH FLOW. CONTINUE WATERING EACH TREE BY HAND ON WASH "GATOR BAIT" ON AN APPROVED MEANS OF IRRIGATION UNIT, WITH ESTABLISHED WATER AT A RATE OF AT LEAST 1" PER WEEK.
- 7.3.10 SPRAY TREES WITH LIQUID OR DUSTABLE FOR CONTROL OF BUGS AND WEAP HARMFUL TO FIRST BRANCH.

- 7.3.11 WHEN A TREE SPACE IS NOT USED:
 - 7.3.12 THE DESTINATION HOLE SHALL BE PREPARED TO THE APPROVED SIZE AND DEPTH PRIOR TO DOING THE TREE. IT TO BE TRANSPORTED. TOPSOIL, WASHED SAND, SHALL BE SET ASIDE IN SEPARATE PILES. THE SOIL SURFACE OF THE HOLE SHALL BE THOROUGHLY WATERED.
 - 7.3.13 A CIRCLE SHALL BE MEASURED AROUND EACH TREE TO THE APPROVED ANTICIPATED SIZE OF THE ROOT BALL. WHERE TREES HAVE BEEN PREVIOUSLY ROOT PRUNED, THE LIMIT SHALL BE ESTABLISHED AT THE TIME OF THE FIRST ROOT PRUNING, WHICH IS 5 INCH FURTHER FROM THE TRUNK THAN THE LINE OF THE ROOT PRUNING.
 - 7.3.14 THE GROUND SHALL BE CLEAN OUT ALONG THE BALL LIMIT WITH A SAW, SHARP SHOULDER OR OTHER MEANS TO A MINIMUM DEPTH OF 12 INCHES.
 - 7.3.15 A TRENCH SHALL BE BUILT OUTSIDE AND ADJACENT TO THIS LIMIT TO A MINIMUM WIDTH OF 1.5 FEET AND AS DEEP AS NECESSARY TO SHAPE A ROOT BALL OF THE APPROVED SIZE.
 - 7.3.16 THE ROOT BALL SHALL BE REMOVED TO PROPER SIZE AND SHAPE.
 - 7.3.17 LOOSENING THE SOIL AROUND THE ROOTS SHALL BE AVOIDED BY CUTTING REMAINING WOODY ROOTS CLEANLY WITH SHARP SHOULDER OR OTHER APPROVED MEANS. EXTREME CARE SHALL BE EXERCISED TO PRESERVE ANY REMAINING ROOTS WHICH HAVE DEVELOPED IN ROOT-PRUNED ZONES. ROOT BALLS SHALL BE SECURELY CONTAINED BY WRAPPING IN BURLAP SECURED TIGHTLY WITH "GATOR BAIT" TWINE. A WOODEN "GATOR BAIT" OR OTHER MEANS WHICH SHALL ENSURE A SOLID, SECURE ROOT BALL. THE LOWER 3 FEET OF TREE TRUNK SHALL BE WRAPPED IN BURLAP IF IT IS ANTICIPATED THAT ANY TIME THERE WILL BE IN CONTACT WITH THE TRUNK.
 - 7.3.18 TREES SHALL BE MOVED BY GRAPES, WHICH ON OTHER APPROVED MEANS FOR THE SUBCONTRACTOR'S APPROVED PLAN TO THE NEW LOCATION. PLANTS SHALL BE HANDLED SO THAT THE ROOT BALL WILL NOT BE LOOSED OR BROKEN AND SHALL BE SET WITH THE SAME COMPASS ORIENTATION AND AT THE SAME RELATIVE ELEVATION AS THEIR ORIGINAL LOCATION.
 - 7.3.19 THE PIT AROUND THE ROOT BALL SHALL BE BACKFILLED, BEGINNING WITH STOCK PILE SUBSOIL. AFTER THE SOIL HAS BEEN THOROUGHLY FIRMED AROUND THE LOWER HALF OF THE BALL, ANY BURLAP SHALL BE CUT AWAY FROM UPPER HALF OF THE BALL AND THE REMAINING BURLAP ADJUSTED TO PREVENT THE FORMATION OF AIR POCKETS. SOIL SHALL BE FIRMED AT 8 INCH INTERVALS AND THOROUGHLY SETTLED WITH WATER THE SAME DAY OF PLANTING TO WITHIN 8 INCHES OF THE FINISH GRADE.
 - 7.3.20 HYDROLYSAL FERTILIZER SHALL BE EVENLY SPREAD ON THE SURFACE OF THE EXCAVATED AREA AT THE RATE OF ONE POUND PER 8 SQUARE FEET. EXCAVATED AREAS SHALL BE BROUGHT TO GRADE WITH STOCKPILED TOPSOIL, AND THE TOP 8 INCHES SHALL BE THOROUGHLY MIXED TO INCORPORATE THE HYDROLYSAL FERTILIZER.
 - 7.3.21 THE PLANTING AREA INCLUDING THE ROOT BALL OF THE TREE SHALL BE WATERED THOROUGHLY.

- 7.4. FINISHING SURFACE: AFTER BACKFILLING, THE CONTRACTOR SHALL CULTIVATE AND RAKE OVER FINISHED PLANTING AREAS AND SHALL LEAVE THEM IN AN IDEAL CONDITION.
- 7.5. DOING FOR SOIL TRANSPORTATION
 - 7.5.1 TRENCHING: DO NOT TRENCH OUTSIDE PREVIOUSLY DOG FOR ROOT PRUNING.
 - 7.5.2 DO NOT DAMAGE NEW ROOTS. DO NOT PERMIT CRACKING OF ROOTBALL OR LOSS OF SOIL. PROTECT ROOTBALL BY COMPLETELY WRAPPING WITH BURLAP PER STANDING HIGHEST PRACTICES.

8. TREATING TRUNK AND CROWN BRANCHED
 - 8.1. REPAIRING DAMAGED BARK AND TRUNK WOUNDS
 - 8.1.1 IN THE EVENT OF BARK OR TRUNK DAMAGE, REMOVE LOOSE BARK(S) BUT TAKE EXTRA CARE NOT TO CUT NOT TO CUT INTO LIVING TISSUE. ALL DAMAGED BARK OR TRUNK SHALL BE CLEANLY SEWED OR CUT BY AN APPROVED MEANS WITH CLEAN, SHARP TOOLS TO PROMOTE CALLUS FORMATION AND MOIST CLOSING.

9. FIELD QUALITY CONTROL
 - 9.1. MAKE WRITTEN REQUEST FOR INSPECTION AFTER PLANTING OPERATIONS ARE COMPLETE.
 - 9.2. SUBMIT REQUESTS FOR INSPECTION TO OWNER AT LEAST TWO (2) DAYS PRIOR TO ANTICIPATED INSPECTION DATE.

10. AFTER TRANSPORT CARE
 - 10.1. STAKING
 - 10.1.1 ALL STAKING/MEDICAL SUPPORT SHALL BE DONE IMMEDIATELY AFTER PLANTING AND ALL STAKES AND WIRE MAINTAINED. PLANTS SHALL STAND PLUMB AFTER STAKING. STAKES SHALL BE PLACED OUTSIDE OF THE ROOT BALL AND SHALL BE SPACED A MINIMUM OF 3 FEET INTO THE ORGANIC STRIPS SHALL BE FASTENED TO THE TREE WITH MEASUREMENTS BY NOSE AND SHALL BE SET PLUMB UNLESS OTHERWISE DIRECTED BY THE R/LA. EACH TREE SHALL HAVE FOUR STAKES.
 - 10.1.2 TREES SHALL BE ORIENTED AT LEAST QUOTE DURING THE GROWING SEASON AND ADJUSTED AS NECESSARY.
 - 10.1.3 STAKES/MEDICAL SUPPORT SHALL BE REMOVED AFTER ONE YEAR OR UNTIL THE TREE IS ESTABLISHED.
 - 10.2. MULCHING
 - 10.2.1 THE CONTRACTOR SHALL APPLY 3 INCH LAYER OF ORGANIC MULCH (SEE 4.2.3) OVER THE ROOT SYSTEM OF THE TRANSPORTED TREES. THE MULCH SHALL EXTEND AS FAR FROM THE TREE AS PRACTICAL TO THE LANDSCAPE SITE.
 - 10.2.2 THE MULCH SHALL NOT BE APPLIED DEEPER THAN 4 INCHES AND SHALL NOT BE TIED AGAINST THE TRUNK (SEE DETAIL SHEET 1/13).



- 10.3. POST-PLANTING FERTILIZATION
 - 10.3.1 APPLY FERTILIZER 30-45 DAYS AFTER INSTALLATION.
 - 10.3.2 INJECT SPECIFIED MATERIAL WITH HIGH PRESSURE INJECTOR INTO SOIL TO DEPTH AND DIAMETER SHOWN BELOW.

TREE CALIPER	APPLICATION POINT	DEPTH	RADIUS	APPLICATION RATE PER TREE
UNDER 2"	3"	1"	15"-18"	1-1
2"-4"	4"	1"	18"-24"	1-1
4"-6"	4"	1"	24"-36"	2-2 GAL.
6"-8"	4"	1"	36"-48"	3 GAL.
ABOVE 8"	3" O.C.	1"	DIAPHRAM	3 GAL./100 SF OF ROOT AREA

- 10.4. IRRIGATION AND DRAINAGE
 - 10.4.1 SLOW OVER THE ENTIRE ROOT ZONE, KEEP THE TOP 2 INCHES MOIST BUT AVOID OVERWATERING. WATER AT A RATE OF 1 INCH PER WEEK. AVOID SHALLOW WATERING.

- 10.5. MONITORING DISEASE AND HAZARD
 - 10.5.1 DESPITE THE BEST EFFORT TO SAVE TREES, SOME TREES MAY NOT RECOVER FROM EXISTING DAMAGE, INCURRED DANCE, OR STRESS CAUSED BY CONSTRUCTION/LANDSCAPE OPERATIONS. THE CONTRACTOR SHALL OBSERVE AND REPORT TO THE R/LA/OWNER.

11. PLANT MAINTENANCE
 - 11.1. TREE AND SHRUB MAINTENANCE: THE CONTRACTOR SHALL MAINTAIN ALL TRANSPORTED AREAS. MAINTAIN PLANTED TREES AND SHRUBS WITHIN THE SPECIFIED TIME FRAME. THE CONTRACTOR SHALL MAINTAIN PLANTED TREES AND SHRUBS WITHIN THE SPECIFIED TIME FRAME. THE CONTRACTOR SHALL MAINTAIN PLANTED TREES AND SHRUBS WITHIN THE SPECIFIED TIME FRAME.



OPTION 1
APPLY THE PLASTIC SHEETING LOOSELY AROUND THE TRUNK TO LEAVE A 0.5 IN. (12 MM) GAP BETWEEN THE TRUNK AND THE SHEETING.

OPTION 2
TWO-WALLED PLASTIC SHEETING OR TRICE SHELLER MATERIAL APPLIED FROM TRUNK PLANE TO FIRST BRANCH SUFFICIENT OVERLAP TO COVER ALL BARK.

TREE WRAP SHOULD BE INSTALLED AT TIME OF PLANTING AND BE REMOVED WHEN DIRECTED BY THE LANDSCAPE ARCHITECT, BUT NO LATER THAN 12 MONTHS AFTER PLANTING.

CERTIFIED ARBORIST



CERTIFIED ARBORIST
Dennis Dix Dixon

Expires: 12/31/2012

BC Consultants
Planners - Engineers - Surveyors - Landscape Architects
12000 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)449-8100 (fax)
www.bcconsult.com




CONCEPTUAL/FINAL DEVELOPMENT PLAN
TREE TRANSPLANTATION SPECIFICATIONS AND DETAILS
CALLAWAY
JAMES W. CALLAWAY
LANDSCAPE ARCHITECT
FAIRFAX COUNTY, VIRGINIA

DESIGNED BY: CAD	REVISIONS
DRAFTED BY: CAD	12-02-11
CHECKED BY: CAD	12-02-11
DATE: JULY, 2011	12-02-11
SCALE: 1/8" = 1'-0"	12-02-11
MEMO:	12-02-11
SHEET 15 OF 22	12-02-11
CO. NO.	12-02-11
CAD NAME: F11524TRP	12-02-11
LAYOUT: TRP-DETAILS	12-02-11
FILE NO: 11524-08	12-02-11


1 COMMUNITY PARK AMENITY AREA
16

SCALE: 1"=10'



2 ENTRY FEATURE AMENITY AREA
16

SCALE: 1"=10'



POLE LIGHT 1

APPROXIMATE LOCATIONS OF THE STREET LIGHTS ARE SHOWN ON THE PLAN. THE FINAL NUMBER AND LOCATIONS OF THE LIGHTS MAY CHANGE WITH FINAL ENGINEERING AND A PHOTOMETRIC ANALYSIS.

MANUFACTURER: HOLOPHANE

MODEL: HP19712 WITH CUT-OFF

LUMINAIRE OR EQUAL

POLE: 14' HIGH

COLOR: BLACK

LAMP: 150 MH

NOTE: INSTALL PER MANUFACTURER'S SPECIFICATION

OR APPROVED EQUAL



A STREET LIGHT

NOT TO SCALE

BA-3103_Poelzl-Grandy_1




BENCH

PHOTO

NOT TO SCALE

2.38 = All 10 percent



3 TOT LOT AMENITY AREA

SCALE: 1"=10'




TRELLIS

NOT TO SCALE



STONE RETAINING AND/OR SOUND WALL


NOT TO SCALE



POSSIBLE ENTRY SIGN

NO SCALING

BC Consultants
Planners • Engineers • Surveyors • Landscape Architects
12600 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)449-8100 (703)449-8108 (Fax)
www.bcva.com




CONCEPTUAL/FINAL DEVELOPMENT PLAN

AMENITY PLAN
CALLAWAY

Madison district

BC REVISIONS	REVISED 02-17-12
08-05-11	REVISED 03-28-12
	REVISED 01-09-11
	REVISED 12-07-11
	REVISED 01-08-12
	REVISED 04-30-12
	REVISED 01-30-12
	REVISED 05-18-12
HIGHWAY 305 V. LLC 1111 SUNSET HILLS ROAD HUNTERDON, VA 20180	
DESIGNED BY: PLR	
DRAFTED BY: PLR	
CHECKED BY: CAD	
DATE: JULY, 2011	
SCALE:	HOR. AS SHOWN VERT. 1"=40'
SHEET 16 OF 22	
CO. NO.	
CAD NAME: F11524AME	
LAYOUT: AMENITY	
FILE NO. 11524-08	

NO SCALE




NO SCALE




NO. SCAL.

MAISON DISTRICT


BC REVISIONS	08-08-11	REVISED 02-17-12
	08-08-11	REVISED 05-28-12
	DESIGNED BY: PLR	
	CHECKED BY: PLR	
	DATE: JULY, 2011	
	SCALE: HOR. AS SHOWN	
	VERT. N/A	
	SHEET 17 OF 22	
	CD. NO.	
	CAD NAME: F115244-EL-2	
	LAYOUT: ELEVATIONS	
	FILE NO. 115244-08	




SECTION A SCALE 1"=20'




SECTION B SCALE 1"=20'



KEY PLAN NO SCALE



SECTION C SCALE 1"=20'



SECTION D SCALE 1"=20'




SECTION E SCALE 1"=20'

BC Consultants
Planners - Engineers - Surveyors - Landscape Architects
12000 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)449-8100 (Fax)
www.bccn.com



CONCEPTUAL/FINAL DEVELOPMENT PLAN
ILLUSTRATIVE SECTIONS
CALLAWAY
MAJOR INTERIOR
FAIRFAX COUNTY, VIRGINIA


DESIGNED BY: PLR	REVISIONS
DRAFTED BY: CAD	01-05-11
CHECKED BY: PLR	REVISION 01-05-11
DATE: JULY, 2011	REVISION 01-05-11
SCALE: HOR. AS SHOWN	REVISION 01-05-11
NOT. 6A	REVISION 01-05-11
SHEET 18 OF 22	REVISION 01-05-11
CO. NO.	REVISION 01-05-11
CAD NAME: F11524ELE	REVISION 01-05-11
LAYOUT: ELEVATIONS	REVISION 01-05-11
FILE NO. 11524-08	REVISION 01-05-11




1 ROAD FRONTAGE IMPROVEMENTS PLAN SCALE: 1"=80'




2 PUBLIC ACCESS DIAGRAM SCALE: 1"=100'




3 POND OVERLOOK AMENITY AREA SCALE: 1"=20'



4 WILLOW RUN DRIVE SECTION A - A SCALE: 1"=1'



5 LITTLE RIVER TURNPIKE SECTION B - B SCALE: 1"=1'



6 POND OVERLOOK AMENITY AREA SECTION C - C NO SCALE

BC Consultants
Planners - Engineers - Surveyors - Landscape Architects
12000 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)449-8100 (703)449-8108 (fax)
www.bcconsultants.com



CONCEPTUAL/FINAL DEVELOPMENT PLAN
STREET SECTIONS AND PLANS
CALLAWAY
JAMES B. CALLAWAY
FAIRFAX COUNTY, VIRGINIA

DESIGNED BY: PLR
DRAFTED BY: CAD
CHECKED BY: PLR
DATE: JULY, 2011
SCALE: HOR. AS SHOWN
VERT. 1"=10'

SHEET 19 OF 22
CD. NO.
CAD NAME: F11514\ST SECTIONS
LAYOUT: SECTIONS
FILE NO. 11524-08



A TOTAL OF 8.79 ACRES OF THE SITE FLOWS TO OUTFALL POINT 'K' IN EXISTING CONDITIONS. WITH THE POST-DEVELOPED CONDITION, APPROXIMATELY 7.8 ACRES ONSITE AREA WILL OUTFALL AT POINT 'K' AFTER BEING DETAINED IN THE UNDERGROUND DETENTION FACILITY. THERE IS ABOUT 1.8 ACRES THAT IS UNDETAINED SHEET FLOW AND ABOUT 0.1 ACRES OF THE ONSITE AREA BYPASSES OUTFALL POINT 'K'. THE PEAK RATE OF RUNOFF FOR THIS AREA IS 7.8 CFS PER ACRE (DO NOT EXCEED THE PREDEVELOPED PEAK RATE). THEREFORE, PER PF1 SECTION 6-0202B, THE PROJECT MAY CONTINUE TO DISCHARGE STORMWATER VIA SHEET FLOW INTO THE LOWER LYING PROPERTY. WE DO NOT ANTICIPATE CHANGES TO DRAINAGE DIVIDES.

THE DETENTION MOUND HAS BEEN UTILIZED IN SIGZAGGING THE FACILITY. THIS THE 1-YEAR STORM WILL BE DETAINED IN THE FACILITY FOR 24-HOURS AND PROPORTIONAL IMPROVEMENTS WILL BE APPLIED TO THE 2- AND 10-YEAR STORM EVENTS. EXTENT OF IMPROVEMENT WILL BEGIN AT POINT "A" AND THE TOTAL, ACROSS AT THIS OUTFALL POINT IS 45.41 ACRES. THE DETENTION MOUND IS LOCATED AT THE DOWNSTREAM END OF THE CHANNEL BEGINNING WITH A STORM CULVERT CROSSING UNDER RANDOLPH DRIVE. THE CHANNEL THEN CROSSES THE FRONT YARDS OF SEVERAL LOTS WITH DRIVEWAY CULVERTS. AT POINT "B" THE RUNOFF OUTFALL IS INTO INDIAN RUN. POINT "B" IS AT THE CONFLUENCE POINT FOR THE EXISTING FACILITY. THIS POINT OF DETENTION DRAINAGE AREA IS 68.7 ACRES. THE CONTRIBUTING DRAINAGE AREA TO THIS POINT IS PROXIMATELY 100 ACRES, WHICH IS AT LEAST 90% OF THE OVERALL DRAINAGE AREA OF 68.7 ACRES. THE EXTENT OF REVIEW WILL END 150' DOWNSTREAM OF POINT "B", AS DEFINED IN PM F-62023.24.

REVIEW OF OUTFALL CONDITIONS ALSO END AT POINT 'B', THE DRAINAGE AREA AT THIS POINT REACHES A FLOODPLAIN THAT DRAINS AN AREA OF AT LEAST ONE SQUARE MILE, WHICH MEET REQUIREMENTS OF THE ZONING ORDINANCE (ZO 18-202 PARAGRAPH 10.F(2)(C)).




BC Consultants
Planners • Engineers • Surveyors • Landscape Architects
12000 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)449-8100 (703)449-8108 (Fax)
www.bccon.com



CONCEPTUAL/FINAL DEVELOPMENT PLAN
EXTENT OF REVIEW AND OUTFALL NARRATIVE
CALLAWAY

WAGON DISTRICT
TAHLEAH COUNTY, VIRGINIA

[illegible]

[illegible]

BMP FACILITY DESIGN CALCULATIONS	
Plan Name: <u>CALLAWAY</u>	Date: <u>April 2012</u>
Plan Number: <u>04-000000 Subwatershed</u>	Engineer: <u>DC Consultants</u>
Site Area (acres): <u>8.80</u>	

E. WATERSHED INFORMATION

PART 1. LIST ALL OF THE SUBAREAS AND "C" FACTORS USED IN THE BMP COMPUTATIONS

SUBAREA DESIGNATION & DESCRIPTION	"C"	AREA (AC.)
(1)	(2)	(3)
B1 RPA	0.30	0.49
B2 Onsite to Extended Detention	0.58	7.44
B3 Onsite Uncontrolled	0.38	0.87
B4 Offsite to Extended Detention	0.45	3.12

PART 2. COMPUTE THE WEIGHTED AVERAGE "C" FACTOR FOR THE SITE

(A) AREA OF THE SITE

	=	<u>8.80</u>	ACRES
--	---	-------------	-------

(B) SUBAREA DESIGNATION

SUBAREA DESIGNATION	"C"	AREA (AC.)	PRODUCT
(1)	(2)	(3)	(4)
B1 RPA	0.30	X 0.49	= 0.15
B2 Onsite to Extended Detention	0.58	X 7.44	= 4.33
B3 Onsite Uncontrolled	0.38	X 0.87	= 0.33
B4 Offsite to Extended Detention	0.45	X 3.12	= 0.00
(b) TOTAL			= <u>4.80</u>

(C) WEIGHTED AVERAGE "C" FACTOR

	=	<u>0.55</u>
--	---	-------------

PART 3. COMPUTE THE TOTAL PHOSPHORUS REMOVAL FOR THE SITE

SUBAREA DESIGNATION	BMP TYPE	REMOVAL EFF. (%)	AREA RATIO	"C" FACTOR RATIO	PRODUCT
(1)	(2)	(3)	(4)	(5)	(6)
B1 RPA		70	X 0.06	X 1.00	= 4.20
B2 Onsite to Extended Detention		40	X 0.85	X 1.06	= 36.70
B3 Onsite Uncontrolled		0	X 0.10	X 0.69	= 0.00
B4 Offsite to Extended Detention		40	X 0.35	X 0.82	= 2.30
100% Credit for Offsite Areas					
(b) TOTAL					= <u>42.20</u>

PART 4. DETERMINE COMPLIANCE WITH PHOSPHORUS REMOVAL REQUIREMENT

(A) SELECT REQUIREMENT

(A) SELECT REQUIREMENT	(A)	<u>40</u>	%
OR (A) FAIRFAX COUNTY CHESAPEAKE BAY PRESERVATION AREA - 60%			
OR (A) FAIRFAX COUNTY WATER SUPPLY OVERLAY DISTRICT - 50%			

(B) IF LINE 3 (A) 42.20 % > LINE 4 (A) 40 %

THEN PHOSPHORUS REMOVAL REQUIREMENT IS SATISFIED.

OUTFALL 'A' PRE-DEVELOPMENT TIME OF CONCENTRATION CALCULATOR

Segment #1: To: TR-55 Sheet
Manning's n: .1300
Hydraulic Length: 100.00 ft
2%r, 24hr P: 3.2000 in
Slope: .050000 ft/ft
Avg. Velocity: .28 ft/sec

Segment #1 Time: 6.06 min

Segment #2: To: TR-55 Shallow
Hydraulic Length: 793.00 ft
Slope: .030000 ft/ft
Unpaved
Avg. Velocity: 2.79 ft/sec

Segment #2 Time: 6.73 min

Segment #3: To: TR-55 Channel
Flow Area: 33.7000 sq.ft
Wetted Perimeter: 33.30 ft
Hydraulic Radius: 1.01 ft
Slope: .030000 ft/ft
Manning's n: .0500
Hydraulic Length: 192.00 ft
Avg. Velocity: 5.20 ft/sec

Segment #3 Time: .62 min

Total To: 11.40 min

OUTFALL 'A' ONSITE PRE-DEVELOPMENT FLOW SUMMARY

Return Event	Depth In	Rainfall Type	RIF ID
Pre 2	3.2000	Synthetic Curve	Type1: 24hr
Pre 10	5.2000	Synthetic Curve	Type1: 24hr
Pre 1	2.7000	Synthetic Curve	Type1: 24hr

Node ID	Type	Return Event	HYG Vol cu.ft	Trun	Qpeak cfs	Qpeak cfs	Max WSEL ft	Max Pond Storage cu.ft
*OUTFLOW	JCT	2	38713		720.00	13.78		
*OUTFLOW	JCT	10	89168		720.00	32.41		
*OUTFLOW	JCT	1	27749		722.50	9.72		
RAINFALL	AREA	2	38713		720.00	13.78		
RAINFALL	AREA	10	89168		720.00	32.41		
RAINFALL	AREA	1	27749		722.50	9.72		

OUTFALL ANALYSIS COMPUTATIONS OUTFALL A

PART 1. LIST ALL OF THE SUBAREAS WITH CN NUMBERS AND COMPUTE THE AVERAGE CN FOR THE OUTFALL

GOOD FORESTED CONDITION		CN		AREA (AC)		PRODUCT	
(A)	Woods/Good Condition S&D	77	X	8.80	*	677.60	
						0.00	
						677.60	
(B)	WEIGHTED AVERAGE CN					77	
POST DEVELOPMENT		CN		AREA (AC)		PRODUCT	
(C)	Woods/Good Condition S&D	87	X	8.80	*	765.60	
						0.00	
						765.60	
(D)	WEIGHTED AVERAGE CN					87	

PART 2. COMPUTE THE DEPTH OF RAINFALL AT OUTFALL

(A) CALCULATE THE RAINFALL AMOUNT (P) FOR THE 1-, 2-, AND 10-YEAR, 24-HOUR STORM.
(FROM TABLE 6.23 OF THE FPM)

$$P_1 = 2.1" \quad P_2 = 3.2" \quad P_{10} = 5.2"$$

(B) DETERMINE THE RUNOFF DEPTH (d) IN INCHES

$$S = \frac{100}{CN} - 10$$

$$d = \frac{(P - 0.25)^2}{P + 0.85}$$

GOOD FORESTED CONDITION	POST DEVELOPMENT
S = 2.89	S = 1.49
d = 0.87	d = 1.48
d = 1.21	d = 1.82
d = 2.79	d = 3.70

PART 3. CALCULATE THE 1-YEAR POST-DEVELOPMENT VOLUME

(A) DETERMINE TOTAL VOLUME OF WATER TO BE DETAINED FOR 1-YEAR STORM

$$V_1 = \text{DRAINAGE AREA (ACRES)} \times d \text{ (INCHES)} / 12 \text{ (INCHES/FOOT)}$$

$$V_1 = 1.0853 \text{ ac-ft} = 47.276 \text{ cu-ft}$$

(B) SUBTRACT VOLUME DETAINED IN BMP VOLUME (FROM BMP COMPUTATIONS)

$$V_{\text{det}} = V_1 - V_{\text{bmp}}$$

$$V_{\text{det}} = 47.276 \text{ cu-ft}$$

PART 4. DETERMINE ORIFICE SIZE FOR 1-YEAR STORM

(A) MAXIMUM HEAD (H) AT THE REQUIRED 1-YEAR STORAGE FROM THE ELEVATION STORAGE CURVE FOR THE FACILITY.

$$H = 8.00 \text{ ft}$$

(B) PEAK OUTFLOW RATE (Q) AT THE MAXIMUM HEAD FOR DRAIN-DOWN TIME OF 24 HOURS.

$$Q_p = \frac{V_1 - T_d}{0.5 \times 3,600 \times 24}$$

$$Q_p = 1.0846 \text{ cfs}$$

(C) REQUIRED ORIFICE AREA

$$A_{1-TR} = \frac{Q_p}{0.6 \sqrt{64.4h}}$$

$$A_{1-TR} = 0.0004 \text{ sq. ft}$$

(D) MAXIMUM DIAMETER OF CIRCULAR ORIFICE

$$\text{MAXIMUM DIAMETER} = 3.84"$$

PART 5. DETERMINE ALLOWABLE RELEASE

(A) DETERMINE THE VOLUME OF RUNOFF FOR EACH STORM TO BE ANALYZED

$$V = \text{DRAINAGE AREA (ACRES)} \times d \text{ (INCHES)} / 12 \text{ (INCHES/FOOT)}$$

GOOD FORESTED CONDITION	POST DEVELOPMENT
V ₁ = 38.802 cu-ft	V ₁ = 61.332 cu-ft
V ₂ = 89.124 cu-ft	V ₂ = 126.108 cu-ft

(B) DETERMINE THE PROPORTIONAL IMPROVEMENTS FOR EACH STORM TO BE ANALYZED

$$R_i = \left[\frac{1 - \frac{P_i}{P_1}}{1 - \frac{P_1}{P_2}} \right] \times 100$$

$$R_1 = 36.96\%$$

$$R_2 = 35.50\%$$

(C) DETERMINE THE ALLOWABLE PEAK RELEASES

GOOD FORESTED CONDITION RELEASE	PROPORTIONAL IMPROVEMENT RELEASE
Q ₁ = 13.78 cfs	Q ₁ = 8.66 cfs
Q ₂ = 32.41 cfs	Q ₂ = 24.05 cfs
	Q ₂ = 8.54 x (1 - R ₂)

PART 6. MAXIMUM ALLOWABLE OUTFALL

STORM FREQUENCY	PROPORTIONAL IMPROVEMENT RELEASE (CFS)	UNDERTAINED TO OUTFALL A (CFS)	* OFFSITE DETAINED (CFS)	MAX. ALLOWABLE OUTFLOW (CFS)
Q ₁ =	8.66	1.68		6.98
Q ₂ =	24.05	6.85	2.71	17.81

OUTFALL 'A' ONSITE UNCONTROLLED FLOW SUMMARY

Return Event	Depth In	Rainfall Type	RIF ID
2	3.2000	Synthetic Curve	Type1: 24hr
10	5.2000	Synthetic Curve	Type1: 24hr
1	2.7000	Synthetic Curve	Type1: 24hr

Node ID	Type	Return Event	HYG Vol cu.ft	Trun	Qpeak min	Qpeak cfs	Max WSEL ft	Max Pond Storage cu.ft
*OUTFLOW	JCT	2	10705		715.50	4.62		
*OUTFLOW	JCT	10	20997		715.50	8.85		
*OUTFLOW	JCT	1	8274		715.50	3.59		
UNDETAINED	AREA	2	10705		715.50	4.62		
UNDETAINED	AREA	10	20997		715.50	8.85		
UNDETAINED	AREA	1	8274		715.50	3.59		

DETENTION VOLUME

Elevation (ft)	Planimeter (sq.in)	Area (sq.ft)	A1+A2+sqrt(A1*A2) (sq.ft)	Volume (cu.ft)	Volume Sum (cu.ft)
270.30	-----	0	0	0	0
272.00	-----	52	52	29	29
274.00	-----	2265	2265	1773	1803
276.00	-----	4893	10484	6980	8783
278.00	-----	8068	19230	12820	21612
280.00	-----	11901	29755	19837	41449
282.00	-----	15921	41587	27729	69174
284.00	-----	19787	53457	35638	104812
284.10	-----	19800	53361	1979	106791

POND VOLUME EQUATIONS

* Incremental volume computed by the Conic Method for Reservoir "Volumes."

$$\text{Volume} = (1/3) \times (EL2 - EL1) \times (Areal + Area2 + \text{sq. rt.}(Areal \times Area2))$$

Where: EL1, EL2 = Lower and upper elevations of the Incremental
Areal, Area2 = Areas computed for EL1, EL2, respectively
Volume = Incremental volume between EL1 and EL2

DETENTION FACILITY DISCHARGE SUMMARY

Return Event	Total Depth In	Rainfall Type	RIF ID
1	2.7000	Synthetic Curve	Type1: 24hr
2	3.2000	Synthetic Curve	Type1: 24hr
10	5.2000	Synthetic Curve	Type1: 24hr
100	7.3000	Synthetic Curve	Type1: 24hr
150	10.9500	Synthetic Curve	Type1: 24hr

MASTER NETWORK SUMMARY

SCS Unit Hydrograph Method

(*Node=Outfall; *Node=Divergence;)
(Trun= HYG Truncation; Blank=Honey L=Left; R=Right; LR=Left&Right)

Node ID	Type	Return Event	HYG Vol cu.ft	Trun	Qpeak min	Qpeak cfs	Max WSEL ft	Max Pond Storage cu.ft
DRY POND	III	POUND	1	55778		716.00	22.48	
DRY POND	III	POUND	2	72163		716.00	29.56	
DRY POND	III	POUND	10	141547		716.00	56.86	
DRY POND	III	POUND	100	217432		716.00	85.51	
DRY POND	III	POUND	150	352004		716.00	134.70	
DRY POND	OUT POND	1	55778		797.00	1.24	278.67	27448
DRY POND	OUT POND	2	72163		732.00	5.29	279.02	30765
DRY POND	OUT POND	10	141546		727.00	112.32	281.14	56245
DRY POND	OUT POND	100	160316		718.00	89.17	282.07	70275
DRY POND	OUT POND	150	294889		718.00	129.02	282.41	75846
ON SITE	AREA	1	55778		716.00	22.48		
ON SITE	AREA	2	72163		716.00	29.56		
ON SITE	AREA	10	141547		716.00	56.86		
ON SITE	AREA	100	217432		716.00	85.51		
ON SITE	AREA	150	352004		716.00	134.70		

BWM FACILITY
RELEASE FLOW RATES

BC Consultants
Planners - Engineers - Surveyors - Landscape Architects
12800 Fair Lakes Circle, Suite 100, Fairfax, VA 22033
(703)445-1000
www.bcconsultants.com



CONCEPTUAL/FINAL DEVELOPMENT PLAN
STORMWATER MANAGEMENT COMPUTATIONS
CALLAWAY
JAMES HARRIS
FAIRFAX COUNTY, VIRGINIA

DESIGNED BY: PLR
DRAFTED BY: CAD
CHECKED BY: PLR
DATE: JULY, 2011
SCALE: HWM N/A
VERT. N/A
SHEET 22 OF 22
CO. NO.
CAD NAME: F11524-SWM
LAYOUT: FDP-SWM2
FILE NO. 11524-08



County of Fairfax, Virginia

MEMORANDUM

DATE: April 2, 2012

TO: Barbara Berlin, Director
Zoning Evaluation Division
Department of Planning and Zoning

FROM: Angela Kadar Rodeheaver, Chief
Site Analysis Section
Department of Transportation

FILE: 3-4 (RZ 2011-MA-029)

SUBJECT: Transportation Impact, Addendum

REFERENCE: RZ/FDP 2011-MA-029 Neighborhoods VI, LLC - Callaway
Traffic Zone: 1408
Land Identification Map: 71-2 ((1)) 36, ((10)) 17A, ((13)) 1

Transmitted herewith are the comments from the Department of Transportation with respect to the referenced application. These comments are based on plats made available to this office dated July 2011, and revised through March 28, 2012. The applicant wishes to rezone the 8.79 acre site from R-2 to PDH-4 for 31 single family dwelling units for a density of 3.52 dwelling units per acre. Access will be to Willow Run Drive. VDOT concurs with this access and has approved a waiver of the access distance from Little River Turnpike.

The applicant has made several revisions to the originally submitted plan including decreasing the number of dwelling units, increasing the number of guest parking spaces, and changing the access from the service road to Willow Run Drive. The latter change was necessitated for several reasons which are discussed below:

- Access to existing Service Road: When Little River Turnpike is widened to six lanes the existing service road will be eliminated and access would be directly to Little River Turnpike which neither VDOT nor Fairfax County would support because of the volume of traffic on that road. Such an access point would not meet VDOT's access management standards and would not give the site access to the signal at Willow Run Drive.
- Access to the service road and extension of the service road to Willow Run Drive and the future signal: Neither VDOT nor Fairfax County would support this access for the same reasons as above; when Little River Turnpike is widened, the existing service road is eliminated, access would be directly to Little River Turnpike and that is not permissible by either VDOT or Fairfax County. In addition, VDOT will not allow the extension of the service road to Willow Run Drive because it would be too close to the signal and create too many conflicts with traffic there.

- Access to Randolph Drive at the southern portion of the site: While it may be allowed by VDOT, this proposed access would go through the Resource Protection Area (RPA). According to the Chesapeake Bay Preservation Ordinance, roads may be exempt from the RPA if an RPA encroachment exception has been filed that shows that there is no other viable alternative. However, in this case no RPA encroachment exception was filed by the applicant because there is a viable alternative from Willow Run Drive.
- Shared access: A shared access with the commercial property to the west either at the service drive or at the southern end of the existing commercial property has never been formally proposed by the applicant. A connection to the service drive would be supported by VDOT only if access is also provided to the signal at Willow Run Drive as currently shown on the plan. A shared access has the same problem as the access to the service drive stated above, when Little River Turnpike is widened the existing service drive would be eliminated, direct access would not be permitted, and the connection would be closed.

A shared access at the southern end of the existing commercial property connecting to Randolph Drive would have the same issues as the connection to Willow Run Drive had in that it would require an access exception from VDOT who would require the access to Willow Run Drive also. Plus, this access was not a consideration in the Plan Amendment and would go through private property that is not part of the zoning case.

After due consideration it was determined that the proposed access from Willow Run Drive as shown on the current plan is the best alternative because it is not temporary as access to the service drive would be, it does not traverse an RPA which is not allowed, it is the most logical access to a public street, and it gives the proposed community access to the signal at Little River Turnpike. The proposed access is as far as possible from the signal thereby reducing vehicular conflicts.

AKR/LAH/lah



County of Fairfax, Virginia

MEMORANDUM

DATE: May 7, 2012

TO: Billy O'Donnell, Staff Coordinator
Zoning Evaluation Division
Department of Planning and Zoning

FROM: Beth Forbes, Engineer *BF*
Site Code Research & Development Branch, providing comments for
Site Development & Inspections Division
Department of Public Works and Environmental Services

SUBJECT: Rezoning/Final Development Plan Application #RZ/FDP 2011-MA-029,
Neighborhoods VI – Callaway, Conceptual/Final Development Plan dated
30 April 2012 and draft Proffers dated 2 May 2012, LDS Project #25234-
ZONA-001-5, Tax Map #71-2-01-0036, #71-2-13-0001 and #71-2-10-0017A,
Mason District

We have reviewed the subject application and offer the following stormwater management comments.

Chesapeake Bay Preservation Ordinance (CBPO)

There is Resource Protection Area (RPA) on this site. A site-specific, field-verified RPA delineation study has been recently approved, #25234-RPA-001-1. Both the county-mapped RPA boundary and the delineated RPA boundary are shown on a number of the sheets.

Disturbance within the RPA has been proposed:

- Invasive species management within the RPA (Sheet 13) will require written authorization from the DPWES director (CBPO 118-3-3(d)). Any vegetation removed from the RPA must be replaced with other vegetation that is equally effective in retarding runoff, preventing erosion, and filtering nonpoint source pollution.
- A trail is proposed to be constructed within the RPA; at the subdivision plan stage a letter from the director of DPWES will be required to approve this exempt use (CBPO 118-5-3(a)).
- Stream restoration and either the combined spillway of the dry pond or a storm drain system are proposed for the RPA. These items are allowed uses; approval by the director is required. A Water Quality Impact Assessment (WQIA) for the work for these items can be submitted in conjunction with the subdivision's construction plan (CBPO 118-2-1(b)).
- Should disturbance within the RPA be necessary to construct the dry pond or underground detention facility, the disturbance would be considered redevelopment in the RPA. As an

Department of Public Works and Environmental Services
Land Development Services, Site Development and Inspections Division
12055 Government Center Parkway, Suite 535
Fairfax, Virginia 22035-5503
Phone 703-324-1720 • TTY 711 • FAX 703-324-8359



allowed use, approval by the director is required for the redevelopment. The required WQLA would be submitted in conjunction with the subdivision's construction plan (CBPO 118-4-4).

- Should a portion of the pond or the underground detention facility encroach into the RPA, an approved encroachment exception request under CBPO 118-6-9, a General Resource Protection Area Exception, will be required before the subdivision construction plan can be approved. A Water Quality Impact Assessment would be submitted concurrently. A public hearing would be a part of the process. (See Proffer subheading.)

Water quality controls are required for this development (PFM 6-0401.2A). A dry pond is depicted on the plat. If the underground detention alternative is chosen, Filterra units and underground filters would be provided to meet the water quality control requirements. An innovative BMP form must accompany the site plan submission if Filterras and underground filtering facilities are proposed (PFM 6-0402.4). These facilities cannot be within storm drain easements since they will be maintained by the homeowners association.

Floodplain

There are no regulated floodplains on the property.

Downstream Drainage Complaints

There is a 2008 erosion complaint on file from a homeowner on Randolph Drive.

Storm Drainage System

The existing channel in the vicinity of lots 23 and 24 has been proposed to be rerouted into a storm drain system. This storm drain will have to be placed in a maintenance easement (PFM 6-0902.2I) and will revert to an open channel upstream of the RPA boundary.

The current drawings show the storm drain system discharging to the pond with pipes constructed underneath a retaining wall (Sheet 21). Construction plans showing this alignment will not be approvable (PFM 6-0902.2I).

No trees will be allowed to be planted within 5 feet of a storm drainage easement that contains a pipe (PFM 12-0515.6B).

Stormwater Detention

Stormwater detention is required (PFM 6-0301.3). Since the outfall is inadequate, the applicant has chosen to use the Detention Method in order to meet the PFM's outfall requirements (PFM 6-0203.4C). Two alternatives for detention have been proposed.

- Alternative #1: A dry pond.
- Alternative #2: An underground detention facility in the same general location as the first alternative. An underground detention waiver is required to be approved by the Board of Supervisors in conjunction with the zoning approvals (PFM 6-0303.8). A memo detailing the DPWES's recommendation for conditional approval of the underground facility was forwarded to you earlier. The underground facility is proposed to be constructed out of 48- and 84-inch diameter pipe. Only pipe diameters 72 inches and above are routinely approved

Billy O'Donnell, Staff Coordinator

Rezoning/Final Development Plan Application #RZ/FPD 2011-MA-029, Neighborhoods VI – Callaway

May 7, 2012

Page 3 of 3

on construction plans (PFM 6-1306.3H). Pipe diameters as small as 60 inches may be approved as a modification to the PFM.

Site Outfall

The outfall narrative has been provided. The applicant proposes to use the Detention Method to meet the adequate outfall requirements. It should be noted when the Detention Method is employed, an approvable subdivision construction plan will demonstrate that a defined channel exists throughout the extent of review (PFM 6-0203.4C(1) and (3)).

Draft Proffers

Regarding the Draft Proffers dated May 2, 2012:

- Proffer #26 should also encompass any maintenance and inspection requirements placed on the property by the Board in addition to those from county and manufacturer's guidelines.
- Proffer #41 should be an Invasive Plant Species Management Plan only. There is no criteria listed here for any stream restoration plan. Written approval from the director of DPWES is required before any invasive control project is initiated (CBPO 118-3-3(d)).
- It is suggested that a proffer be included to address the dry pond's proximity to the RPA. If, in final design, the extent of the pond will encroach into the RPA it will not be possible to make the pond smaller. A partial detention waiver to decrease the volume requirements of the pond will not be available to this property since the Detention Method will be used to meet the adequate outfall requirements. It is suggested that the applicant include a proffer to delete Lot 19 instead of requesting an RPA encroachment exception to construct a portion of the pond in the RPA.

Please contact me at 703-324-1720 if you require additional information.

BF/

cc: Fred Rose, Chief, Watershed Planning & Assessment Branch, Stormwater Planning Division, DPWES
Bijan Sistani, Branch Chief South, Site Development & Inspections Division, DPWES
Zoning Application File